

***AUGUSTINE***  
***GENERAL ENGINEERING, INC.***

CA. LICENSE #1092409

DIR# 1000920033

August, 1 2022

CITY OF CORONA  
DEPARTMENT OF PUBLIC WORKS  
400 S. VICENTIA AVE  
CORONA, CA. 92880

**RE: Proposal for Installation of 6" Waterline on Brae Burn, Oakland Hills & Cypress Point**

**Work:** Augustine General Engineering (AGE) will provide all labor, materials and equipment to install approximately 1630LF of 6" DI restrained waterline, (4) fire hydrants and (30) 1" water services on Brae Burn, Oakland Hills & Cypress Point in the City of Corona. The work will replace the existing 6" waterline, services and appurtenances which have had multiple failures in the past. Augustine will provide construction services as follows:

- USA DigAlert Notification.
- Provide utility verification for protection and alignment. Need to establish a clear alignment for installation. No sewer main or laterals were observed on these streets. Utility crossings are estimated at (35).
- Mobilization of equipment and materials.
- Trench asphalt saw cutting and/ or grinding.
- Installation of approximately 1630lf of 6" DI restrained mainline pipe w/ (4) 6" X 6" fire hydrant tees, and (1) 6" DI MJ end cap for testing. SE30 sand bedding per STD 406 w/ 3" poly warning tape. Pipe shall be double wrapped w/ polyethylene encasement and shall be installed with a minimum of 36" of cover. Trenches to be backfilled w/ Class II base.
- Installation of (4) fire hydrants per STD 412. (Approximately 30' – 40' long)
- Installation of (30) 1" water services per STD 414. Services range in length from 15' to 60' +/- . Total estimated length of services is 800LF +/- . Service runs to angle meter.
- Provide trench shoring.
- Provide traffic control and onsite trucking.
- Provide chlorination, de-chlorination, leakage testing, flushing and bacteria testing.
- Furnish and install (1) 8" x 6" connection onto existing 8" waterline on Brae Burn.
- Perform system connection.
- Connect (30) new service lines to existing meters.
- Abandon existing 6" watermain in place. Abandon existing fire hydrants. Provide concrete bulkheads at all areas where existing main is cut.
- Provide 2" temporary asphalt over trenches during construction.
- Install 5" base paving per STD 150. (Final overlay optional by City) Final overlay estimated at 54,000SF @ 2".
- Haul away existing spoils to Plant 1.

**Construction Materials & Work Breakdown:**

Pipeline Materials (See attached take off & quote)

SE30 Sand (720 ton Estimated)

Temporary Asphalt (115 Tons Estimated)

Class II Full Trench (1100 Tons Estimated)

Base Paving Asphalt (260 Tons Estimated)

Concrete (5 Yards Estimated)

Bacteria Testing

Labor

Equipment

Insurance

Traffic Control

Shoring

Grinding/ Saw cutting

On Site Trucking

Spoil Haul Away to Plant 1

6" Abandonment @ Existing Valve

Chlorination/ De-chlorination/ Flushing

Total Pipeline : \$633,968.00

2" Grind & Overlay - \$109,000.00

Bonding @ 2% - \$15,250.00

**Complete Total - \$758,218.00**

**Exclusions:**

- Permits/ Permit fees
- Engineered Plans/ Traffic control Plans
- Survey
- Inspection fees
- Compaction/ concrete testing
- SWPPP
- Asphalt grind & Overlay (Optional at City Discretion)
- Builders Risk Insurance/ Insurance beyond \$2,000,000 aggregate
- Water fees
- Striping

**Notes:**

1. Estimated time for completion – (30-35) working days
2. All labor per prevailing wage rates.
3. City to operate all valves.
4. City to provide any replacement water meters.
5. City to provide hydrant meter and water for construction.
6. Pricing was prepared per Augustine's conceptual understanding of the work needed. Field potholing will be necessary to establish pipeline/ appurtenant alignment. Please note that there are multiple options for performing this work, and final pricing can be negotiated based on the actual construction platform determined by the City.
7. All work can be performed as a T&M if preferred by City.
8. Service parts beyond angle meter to be provided by City, including replacement boxes, if needed.
9. Asphalt grind and overlay optional at City request.
10. Due to industry material shortages and continual pricing changes, lead times of all materials and final pricing are subject to delays and potential increases. Pricing is valid for (30) days from quote date. It is anticipated that Ductile Iron pipe has long lead times at present. Optional PVC pipe and fittings may have up to a six week lead time for acquisition.

Augustine General Engineering would like to thank The City of Corona for the opportunity to bid on this project. If you have any questions or need any clarifications, please feel free to call anytime at 909-208-2069.

Mike Lowen  
Augustine General Engineering

Accepted by: \_\_\_\_\_ Date: \_\_\_\_\_

Acceptance of proposal is an agreement of all terms and conditions outlined above.

***AUGUSTINE***  
***GENERAL ENGINEERING, INC.***  
8780 19<sup>TH</sup> ST. BOX #298  
ALTA LOMA CA. 91701  
[augustinepipe@gmail.com](mailto:augustinepipe@gmail.com)  
909-208-2069

**CITY OF CORONA – BURN BRAE, CYPRESS POINT, OAKLAND HILLS WATERLINE REPLACEMENT**

**MATERIAL TAKE OFF:**

**CONNECTION:**

2 – 6" DI MJ COUPLING  
6 – 6" DI MEGALUGS W/ ACC KIT  
2 – 6" PVC MEGALUGS W/ ACC KIT  
1 – 6" HYMAX COUPLING – DI X AC PIPE  
3 – 6" FL X MJ ADAPTOR  
4 – 6" N,B&G KITS – 316SS/ 1/16" GARLOCK 3000 FF (FLANGE KIT)  
1 – 6" DI FLANGED TEE  
1 – 6" FL X MJ GATE VALVE  
1 – 8" VALVE CAP – "WATER"  
1 – 8" X 18" SLIP CAN  
1 – 8" DEBRIS CAP (PLUG INSIDE RISER PIPE)  
1 – 6" BLIND FLANGE

**MAINLINE:**

6 – 6" DI 45° MJ ELBOW  
3 – 6" DI 90° MJ ELBOW  
4 – 6" X 6" DI MJ X MJ X FL TEE  
1 – 6" DI FLANGED TEE  
2 – 6" FL X MJ GATE VALVE  
20LF – 8" CL150 C900 PVC PIPE  
2 – 8" VALVE CAP – "WATER"  
2 – 8" X 18" SLIP CAN  
2 – 8" DEBRIS CAP (PLUG INSIDE RISER PIPE)  
3 – 6" N,B&G KITS – 316SS/ 1/16" GARLOCK 3000 FF (FLANGE KIT)  
1 – 6" FL X MJ ADAPTOR  
35 – 6" DI MEGALUG W/ ACC KIT  
1 – 6" DI MJ END CAP W/ 2" THREADED OUTLET  
1638LF – 6" DI PIPE CL350  
93 – 6" FIELD LOCK GASKETS  
4000LF – 8 MIL V-BIO POLYSLEEVE FOR 6" DI PIPE – BLUE OR CLEAR (DOUBLE WRAP)  
1 – GALLON BITUMASTIC  
2 – ROLL 8-MIL POLY WRAP  
1 – QUART ANTI SEIZE  
3000LF – 3" WIDE BLUE NON DETECTABLE WARNING TAPE

**END CAP TESTING:**

2 – 2" X 12" GALV NIPPLE  
2 – 2" GALV 90 ELBOW  
1 – 2" X 30" GALV NIPPLE  
1 – 2" GALV COUPLING

1 – 2" THREADED BRASS VALVE W/ HAND WHEEL  
1 – 2" GALV PLUG  
1 – 2" GALV STR ELL

**FIRE HYDRANT PER STD 412 (4):**

4 – 6" FL X MJ GATE VALVE  
20LF – 8" CL150 C900 PVC PIPE  
4 – 8" VALVE CAP – "WATER"  
4 – 8" X 18" SLIP CAN  
4 – 8" DEBRIS CAP (PLUG INSIDE RISER PIPE)  
4 – 6" N,B&G KITS – 316SS/ 1/16" GARLOCK 3000 FF (FLANGE KIT)  
12 – 6" DI MEGALUG W/ ACC KIT  
144LF – 6" CL350 DI PIPE  
4 – 6" DI MJ 90 ELBOW  
4 – 6" FIELD LOCK GASKET  
4 – 6" X 96" DI SPOOL PE X FL (8 HOLE FLANGE)  
4 – CLOW FIRE HYDRANT MODEL 850 W/ 8 HOLE PATTERN  
4 – 6" X 6" BREAK OFF SPOOL – 8 HOLE X 8 HOLE  
8 – 3/4" BREAK OFF BOLTS/ 1/16" GARLOCK 3000 FF (8 HOLE SETS) SILICON FILLED  
4 – BLUE DOT REFLECTORS

**1" WATER SERVICE PER STD. 414 (30): (NEW SERVICE TO BE RUN TO EXISTING METER)**

30 – 6" X 1" BRASS SERVICE SADDLE – JONES J969 – IP  
30 – 1" CORP STOP – MIP X COMP – JONES J1935SG  
800LF – 1" TYPE "K" SOFT COPPER  
30 – 1" ANGLE METER – JONES E1963WSG – COMPRESSION

**METERS PROVIDED BY CITY**

**OPTIONAL: (IF CITY ELECTS TO REPLACE)**

30 – DFW DFWPW6C4-12-4F LLPDE METER BOX AND HDPE COVER W/ READING LID H-20 RATING  
LABELED "WATER" – 16 5/15" X 31 3/4" X 12" INSIDE DIMENSIONS  
30 – 1" BRASS METER TAIL PIPE  
30 – 1" METER VALVE – JONES E1900W  
30 – 1" X 3" BRASS NIPPLE  
30 – 1" BRASS UNION  
30 – 1" X 12" BRASS NIPPLE

**ABANDONMENTS:**

1 – 6" HYMAX END CAP

INLAND WATER WORKS SUPPLY CO  
2468 Miramonte Drive  
San Bernardino, CA 92405  
909-883-8941  
Fax 909-881-4041



## Quotation

QUOTATION DATE	QUOTE NUMBER	
07/27/2022	S1058081	
JOB NAME	PAGE NO.	1 of 7

QUOTE TO:

SHIP TO:

AUGUSTINE GENERAL ENGINEERING  
8780 19TH ST  
BOX #298  
ALTA LOMA, CA 91701

AUGUSTINE GENERAL ENGINEERING  
BURN BRAE, CYPRESS POINT, OAKLAND  
HILLS WATERLINE REPLACEMENT  
ALTA LOMA, CA 91701

JOB BID DATE AND TIME		AGENCY		WRITER	
N/A N/A		N/A		LUCY SANCHEZ	
ORDER QTY	DESCRIPTION		UNIT PRICE	EXT PRICE	
	<b>**TO OUR VALUED BUSINESS PARTNERS REGARDING PRICING**</b>  DUE TO CURRENT SUPPLY CHAIN DISRUPTIONS, MATERIALS ARE SUBJECT TO PRICING AT TIME OF SHIPMENT. MATERIAL AVAILABILITY AND TIMELINESS OF SHIPMENTS CANNOT BE GUARANTEED. THIS TERM SUPERSEDES ALL OTHER CONTRACTUAL PROVISIONS.  *****  WE STRONGLY ADVISE YOU TO PUT PROTECTIVE WORDING REGARDING MATERIAL PRICING AND LDs DUE TO LONG LEAD TIMES IN YOUR BID SUBMISSION. THANK YOU AND GOOD LUCK ON THIS BID!  *****  MATERIAL TAKE OFF: CONNECTION:				
2ea	DOMMJSL06LACC		141.094/ea	282.19	
	6" DOMESTIC MJ LONG SLEEVE LACC				
6EA	EBAA1106DEC		63.520/ea	381.12	
	6" EBAA 1106DEC MEGA LUG KIT				
	FITTING RESTRAINT FOR DIP				
2ea	EBAA2006PEC		73.065/ea	146.13	
	6" EBAA 2006PEC MEGA LUG KIT				
	FITTING RESTRAINT FOR C900				
1ea	860-54-0163-16		329.550/ea	329.55	
	6" HYMAX 2 FLIP COUPLING				
	642-768 RANGE				

\*\* Continued on Next Page \*



INLAND WATER WORKS SUPPLY CO  
2468 Miramonte Drive  
San Bernardino, CA 92405  
909-883-8941  
Fax 909-881-4041



## Quotation

QUOTATION DATE	QUOTE NUMBER	
07/27/2022	S1058081	
JOB NAME	PAGE NO.	2 of 7

QUOTE TO:

SHIP TO:

AUGUSTINE GENERAL ENGINEERING  
8780 19TH ST  
BOX #298  
ALTA LOMA, CA 91701

AUGUSTINE GENERAL ENGINEERING  
BURN BRAE, CYPRESS POINT, OAKLAND  
HILLS WATERLINE REPLACEMENT  
ALTA LOMA, CA 91701

JOB BID DATE AND TIME		AGENCY		WRITER	
N/A N/A		N/A		LUCY SANCHEZ	
ORDER QTY	DESCRIPTION		UNIT PRICE	EXT PRICE	
3ea	DOMMJFA06LACC		127.699/ea	383.10	
	6" DOMESTIC MJ X FLG ADAPTER LACC				
4ea	BNSDOM316SS6-8		251.875/ea	1007.50	
	6" - 8" DOMESTIC 316SS BOLT & NUT SET				
4ea	GRNA06		5.000/ea	20.00	
	6" NON ASB NSF61 RING GASKET 1/16				
1ea	DOMFT06		450.965/ea	450.97	
	6" DOMESTIC FLG TEE 124238				
1ea	A2362-1906		881.023/ea	881.02	
	6" MUELLER A-2362 MJ X FLG RW GATE VALVE DI BODY C509 E381 OPEN LEFT				
	2" OP NUT LACC				
1ea	VBC86W		64.200/ea	64.20	
	8" X 6" CI VALVE BOX CAP "WATER"				
1ea	GVCT0818		18.500/ea	18.50	
	8" X 18" GALVANIZED TOP SECTION				
1ea	DC825BLLD8		60.000/ea	60.00	
	8" DEBRIS CAP DC825BL W/ LD8				
1ea	DOMBF06		124.127/ea	124.13	
	6" DOMESTIC BLIND FLANGE				
	MAINLINE:				
6ea	DOMMJ4506LACC		132.164/ea	792.98	
	6" DOMESTIC MJ 45 ELL LACC 072867				
3ea	DOMMJ9006LACC		160.740/ea	482.22	
	6" DOMESTIC MJ 90 ELL LACC 072225				
4ea	DOMMJFT06LACC		286.653/ea	1146.61	
	6" DOMESTIC MJ X FLG TEE LACC				

\*\* Continued on Next Page \*

INLAND WATER WORKS SUPPLY CO  
2468 Miramonte Drive  
San Bernardino, CA 92405  
909-883-8941  
Fax 909-881-4041



## Quotation

QUOTATION DATE	QUOTE NUMBER		
07/27/2022	S1058081		
JOB NAME	PAGE NO.	3 of 7	

QUOTE TO:

SHIP TO:

AUGUSTINE GENERAL ENGINEERING  
8780 19TH ST  
BOX #298  
ALTA LOMA, CA 91701

AUGUSTINE GENERAL ENGINEERING  
BURN BRAE, CYPRESS POINT, OAKLAND  
HILLS WATERLINE REPLACEMENT  
ALTA LOMA, CA 91701

JOB BID DATE AND TIME		AGENCY		WRITER	
N/A N/A		N/A		LUCY SANCHEZ	
ORDER QTY	DESCRIPTION	UNIT PRICE	EXT PRICE		
1ea	DOMFT06 6" DOMESTIC FLG TEE 124238	450.965/ea	450.97		
2ea	A2362-1906 6" MUELLER A-2362 MJ X FLG RW GATE VALVE DI BODY C509 E381 OPEN LEFT 2" OP NUT LACC	881.023/ea	1762.05		
20ft	PVCDR1808B 8" PVC DR18 C900 PIPE BLUE	25.812/ft	516.24		
8ea	VBC86W 8" X 6" CI VALVE BOX CAP "WATER"	64.200/ea	513.60		
2ea	GVCT0818 8" X 18" GALVANIZED TOP SECTION	18.500/ea	37.00		
2ea	DC825BLLD8 8" DEBRIS CAP DC825BL W/ LD8	60.000/ea	120.00		
3ea	BNSDOM316SS6-8 6" - 8" DOMESTIC 316SS BOLT & NUT SET	251.875/ea	755.63		
3ea	GRNA06 6" NON ASB NSF61 RING GASKET 1/16	5.000/ea	15.00		
1ea	DOMMJFA06LACC 6" DOMESTIC MJ X FLG ADAPTER LACC	127.699/ea	127.70		
35EA	EBAA1106DEC 6" EBAA 1106DEC MEGA LUG KIT FITTING RESTRAINT FOR DIP	63.520/ea	2223.20		
1ea	DOMMJCPT06LACC 6" X 2" DOMESTIC MJ TAPT CAP LACC	102.695/ea	102.70		
1638ft	DITJPC35006 6" PC350 TJ DUCTILE IRON PIPE	24.433/ft	40021.25		

\*\* Continued on Next Page \*



INLAND WATER WORKS SUPPLY CO  
2468 Miramonte Drive  
San Bernardino, CA 92405  
909-883-8941  
Fax 909-881-4041



## Quotation

QUOTATION DATE		QUOTE NUMBER	
07/27/2022		S1058081	
JOB NAME		PAGE NO.	4 of 7

QUOTE TO:

SHIP TO:

AUGUSTINE GENERAL ENGINEERING  
8780 19TH ST  
BOX #298  
ALTA LOMA, CA 91701

AUGUSTINE GENERAL ENGINEERING  
BURN BRAE, CYPRESS POINT, OAKLAND  
HILLS WATERLINE REPLACEMENT  
ALTA LOMA, CA 91701

JOB BID DATE AND TIME		AGENCY		WRITER	
N/A N/A		N/A		LUCY SANCHEZ	
ORDER QTY	DESCRIPTION		UNIT PRICE	EXT PRICE	
93ea	GUSFL06 6" FIELD LOK GASKET		68.311/ea	6352.92	
8ea	PWVBIO0308X500 3" - 8" X 500' V-BIO POLY WRAP FOR 3" THRU 8" PIPE		312.155/ea	2497.24	
1ea	K50G HYTECH HT50 LOW VOC BITUMASTIC		56.000/ea	56.00	
2ea	PWC3X100 3' X 100' CLEAR POLY WRAP 8 MIL		35.000/ea	70.00	
1ea	AERVOE9120 AERVOE 9120 12OZ CAN ANTI SEIZE		17.000/ea	17.00	
3ea	TAPENONDETWTR3 3" WIDE NON-DECT TAPE "WATER" END CAP TESTING:		18.000/ea	54.00	
2ea	GN2X12 2" X 12" GALVANIZED NIPPLE		15.000/ea	30.00	
2ea	G902 2" GALVANIZED 90 ELL		20.250/ea	40.50	
1ea	GN2X30 2" X 30" GALVANIZED NIPPLE		40.100/ea	40.10	
1ea	GCPLG2 2" GALVANIZED COUPLING		17.000/ea	17.00	
1ea	MILUP10502 2" MIL NL UP105 BRASS GATE VLV		165.000/ea	165.00	
1ea	GP2 2" GALVANIZED PLUG (CORED)		11.000/ea	11.00	
1ea	GST902 2" GALVANIZED 90 ST ELL		8.000/ea	8.00	

\*\* Continued on Next Page \*

INLAND WATER WORKS SUPPLY CO  
2468 Miramonte Drive  
San Bernardino, CA 92405  
909-883-8941  
Fax 909-881-4041



## Quotation

QUOTATION DATE	QUOTE NUMBER	
07/27/2022	S1058081	
JOB NAME	PAGE NO.	5 of 7

QUOTE TO:

SHIP TO:

AUGUSTINE GENERAL ENGINEERING  
8780 19TH ST  
BOX #298  
ALTA LOMA, CA 91701

AUGUSTINE GENERAL ENGINEERING  
BURN BRAE, CYPRESS POINT, OAKLAND  
HILLS WATERLINE REPLACEMENT  
ALTA LOMA, CA 91701

JOB BID DATE AND TIME		AGENCY	WRITER	
N/A N/A		N/A	LUCY SANCHEZ	
ORDER QTY	DESCRIPTION	UNIT PRICE	EXT PRICE	
4ea	FIRE HYDRANT PER STD 412 (4) A2362-1906	881.023/ea	3524.09	
20ft	6" MUELLER A-2362 MJ X FLG RW GATE VALVE DI BODY C509 E381 OPEN LEFT 2" OP NUT LACC PVC DR1808B	25.812/ft	516.24	
4ea	8" PVC DR18 C900 PIPE BLUE VBC86W	64.620/ea	258.48	
4ea	8" X 6" CI VALVE BOX CAP "WATER" GVCT0818	18.500/ea	74.00	
4ea	8" X 18" GALVANIZED TOP SECTION DC825BLLD8	60.000/ea	240.00	
4ea	8" DEBRIS CAP DC825BL W/ LD8 BNSDOM316SS6-8	251.875/ea	1007.50	
4ea	6" - 8" DOMESTIC 316SS BOLT & NUT SET GRNA06	5.000/ea	20.00	
12EA	6" NON ASB NSF61 RING GASKET 1/16 EBAA1106DEC	63.520/ea	762.24	
144ft	6" EBAA 1106DEC MEGA LUG KIT FITTING RESTRAINT FOR DIP DITJPC35006	24.433/ft	3518.35	
4ea	6" PC350 TJ DUCTILE IRON PIPE DOMMJ9006LACC	160.740/ea	642.96	
4ea	6" DOMESTIC MJ 90 ELL LACC 072225 GUSFL06	68.311/ea	273.24	
	6" FIELD LOK GASKET			

\*\* Continued on Next Page \*

INLAND WATER WORKS SUPPLY CO  
2468 Miramonte Drive  
San Bernardino, CA 92405  
909-883-8941  
Fax 909-881-4041



## Quotation

QUOTATION DATE	QUOTE NUMBER	
07/27/2022	S1058081	
JOB NAME	PAGE NO.	6 of 7

QUOTE TO:

SHIP TO:

AUGUSTINE GENERAL ENGINEERING  
8780 19TH ST  
BOX #298  
ALTA LOMA, CA 91701

AUGUSTINE GENERAL ENGINEERING  
BURN BRAE, CYPRESS POINT, OAKLAND  
HILLS WATERLINE REPLACEMENT  
ALTA LOMA, CA 91701

JOB BID DATE AND TIME		AGENCY		WRITER	
N/A N/A		N/A		LUCY SANCHEZ	
ORDER QTY	DESCRIPTION		UNIT PRICE	EXT PRICE	
4ea	SPOOLDIF0696 6" X 96" DI FLG SPOOL		996.966/ea	3987.86	
4ea	CLOW850DSY8H CLOW 850 DI HYD 8H SAFETY YELLOW 1.5PN		2523.929/ea	10095.72	
4ea	HE68HDOM 6" BO HYDRANT EXTENSION 8 HOLE DOMESTIC		255.294/ea	1021.18	
8ea	SFBOBNS68H SILICONE FILLED BREAK OFF BNS 8H		59.375/ea	475.00	
8ea	GRNA06 6" NON ASB NSF61 RING GASKET 1/16		5.000/ea	40.00	
4ea	BLUEDOT BLUE DOT MARKER ONLY		7.000/ea	28.00	
2ea	BLUEDOTGLUE EPOXY KIT FOR BLUE DOT 1" WATER SERVICE PER STD. 414 (30): (NEW SERVICE TO BE RUN TO EXISTING METER		18.000/ea	36.00	
30ea	J9696X1IP 6" X 1" IP J-969 DOUBLE STRAP BRASS SADDLE W/SS		202.089/ea	6062.67	
30ea	E1935SG1 1" JJ NL MIP X CTSSG B CORP		100.436/ea	3013.08	
800ft	CPKS1100 1" K SOFT COPPER TUBE 100' COILS		9.660/ft	7728.00	
30ea	E1963WSG1 1" JJ NL CTSSG B AMS LW		185.913/ea	5577.39	

\*\* Continued on Next Page \*

INLAND WATER WORKS SUPPLY CO  
2468 Miramonte Drive  
San Bernardino, CA 92405  
909-883-8941  
Fax 909-881-4041



## Quotation

QUOTATION DATE	QUOTE NUMBER
07/27/2022	S1058081
JOB NAME	PAGE NO. 7 of 7

QUOTE TO:

SHIP TO:

AUGUSTINE GENERAL ENGINEERING  
8780 19TH ST  
BOX #298  
ALTA LOMA, CA 91701

AUGUSTINE GENERAL ENGINEERING  
BURN BRAE, CYPRESS POINT, OAKLAND  
HILLS WATERLINE REPLACEMENT  
ALTA LOMA, CA 91701

JOB BID DATE AND TIME		AGENCY		WRITER	
N/A N/A		N/A		LUCY SANCHEZ	
ORDER QTY	DESCRIPTION	UNIT PRICE	EXT PRICE		
	METER PROVIDED BY CITY OPTIONAL" (IF CITY ELECTS TO REPLACE)				
30ea	DFWPW6C4-12-BODY 16 5/16 x 31 3/4 x 12 H DFW METER BOX ONLY	167.614/ea	5028.42		
30ea	DFWPW6C-4F_6450_NHK-LID 30 1/2 X 17 5/8 DFW LID	146.829/ea	4404.87		
30ea	E1301X2.63 1" X 2 5/8" JJ NL MTR CPLG	22.567/ea	677.01		
1ea	E1900W1 1" JJ NL FIP X FIP B CURB LW	133.977/ea	133.98		
30ea	DOMBN1X3 1" X 3" DOMESTIC BRASS NIPPLE	7.000/ea	210.00		
30ea	BU1 1" NL BRASS UNION	75.350/ea	2260.50		
30ea	DOMBN1X12 1" X 12" DOMESTIC BRASS NIPPLE	25.000/ea	750.00		
1ea	ABANDONMENTS: HY867-56-06165-16 6" HYMAX GRIP END CAP (6.50-7.20) NPT2 232PSI	293.981/ea	293.98		
***THANK YOU FOR THE OPPORTUNITY TO BID!***		Subtotal	125235.08		
		S&H Charges	0.00		
		Estimated Tax	9705.72		
		Amount Due	134940.80		