

CONTRASTING COLORED 3" WIDE WARNING STRIPE INTEGRAL TO CONCRETE AT TOP LANDING AND BOTTOM TREAD PER ADA REQUIREMENTS. 4' X 8' METAL LOUVER OPENING FOR VENTILATION. PAINT TO MATCH

BUILDING COLOR. \ HOLLOW METAL DOORS. PROVIDE COMPLETE WEATHER STRIPING ALL AROUND DOOR.

 \langle 9 \rangle EXTERIOR DOWN SPOUTS W/ 2 OVERFLOW SCUPPERS.

 $\langle 10 \rangle$ DOCK DOOR BUMPER TYPICAL. ALUMINUM STOREFRONT FRAMING WITH TEMPERED GLAZING AT ALL DOORS, SIDELITES ADJACENT TO DOORS AND GLAZING WITH BOTTOMS LESS THAN

18" ABOVE FINISH FLOOR ELEVATION. $\langle 12 \rangle$ METAL CANOPY.

(13) KNOCK OUT PANEL.

 \langle 14angle INTERIOR ROOF DRAIN W/ 2 OVERFLOW SCUPPERS.

(15) CONC. FILLED GUARD POST. 6" DIA. U.N.O.. 42"H.

6. CONTRACTOR SHALL FULLY PAINT ONE CONCRETE PANEL W/ SELECTED COLORS. ARCHITECT AND OWNER SHALL APPROVE PRIOR TO PAINTING REMAINDER OF BUILDING. 7. BACK SIDE OF PARAPETS TO HAVE SMOOTH FINISH AND BE PAINTED WITH

ELASTOMERIC PAINT.

8. FOR SPANDREL GLAZING, ALLOW SPACE BEHIND SPANDREL TO BREATH. 9. USE ADHESIVE BACK WOOD STRIPS FOR ALL REVEAL FORMS. 10. THE FIRST COAT OF PAINT TO BE ROLLED-ON AND THE SECOND COAT TO BE SPRAYED-ON

DOOR COLORS : MATCH BUILDING COLOR

CORONADO STONE : BARN WOODSTONE - CANNERY BLEND (9) | ONCRETE TILT-UP PANEL. COLOR: SW7674 PEPPERCORN

SPANDREL: 1/4" VISTACOOL PACIFICA SPANDREL W/ HARMONY BLUE OPACICOAT PAINTED ON REFLECTIVE. MULLIONS: ANODIZED CLEAR

KEYNOTES - FLOOR PLAN

 \langle 1 angle concrete tilt—up panel.

\$\langle 2 \rangle STRUCTURAL STEEL COLUMN. TYPICAL STOREFRONT SYSTEM WITH GLAZING. SEE OFFICE BLOW-UP AND ELEVATIONS $\frac{3}{2}$ for size, color and locations.

CONCRETE RAMP W/ 42"HIGH CONC TILT—UP GUARD WALL OR BUILDING WALL ON BOTH SIDE OF RAMP.

(5) 9' X 10' TRUCK DOOR, SECTIONAL O'H., STANDARD GRADE.

6 EXTERIOR CONCRETE STAIR

 $\sqrt{7}$ 5'-6"X5'-6"X4" THICK CONCRETE EXTERIOR LANDING PAD TYPICAL AT ALL EXTERIOR $\stackrel{\prime}{\smile}$ man doors to landscaped area. Finish to be medium bloom finish. Slope to BE 1/4": 12" MAX. PROVIDE WALK TO HARD SURFACE PER CITY REQUIREMENTS. (8) LOUVERED OPENING FOR VENTILATION.

9 DOCK DOOR BUMPER

(10) 12' X 14' DRIVE THRU. SECTIONAL OH., STANDARD GRADE.

(11) 3'X7' HOLLOW METAL EXTERIOR MAN DOOR.

 $\langle 12 \rangle$ SOFFIT LINE ABOVE

 $\langle 13 \rangle$ NOT USED

(14) CONC. FILLED GUARD POST. 6" DIA. U.N.O.. 42"H.

(15) EXTERIOR DOWNSPOUT WITH OVERFLOW SCUPPER,

 $\langle 16 \rangle$ Z GUARD

(17) APPROXIMATE LOCATION OF ELECTRICAL ROOM

(18) METAL CANOPY

GENERAL NOTES - FLOOR PLAN

A. THIS BUILDING IS DESIGNED FOR HIGH PILE STORAGE WITH FIRE ACCESS MAN DOORS AT APPROXIMATELY 100'. A SEPARATE PERMIT WILL BE REQUIRED FOR ANY RACKING/CONVEYER SYSTEMS.

B. FIRE HOSE LOCATIONS SHALL BE APPROVED PER FIRE DEPARTMENT.

C. SEE "C" DRAWINGS FOR FINISH SURFACE ELEVATIONS.

D. WAREHOUSE INTERIOR CONCRETE WALLS ARE PAINTED WHITE. COLUMNS ARE TO RECEIVE PRIMER ONLY. ALL GYP. BD. WALLS IN WAREHOUSE TO RECEIVE 1 COAT OF WHITE TO COVER.

E. SLOPE POUR STRIP 1/2" TO EXTERIOR AT ALL MANDOOR EXITS. SEE "S" DRAWINGS FOR POUR STRIP LOCATION.

F. ALL DIMENSIONS ARE TO THE FACE OF CONCRETE PANEL WALL, GRIDLINE, OR FACE OF STUD U.N.O.

CONTRACTOR TO VERIFY ACTUAL UTILITY LOCATIONS. PLUMBING/ELECTRICAL COORDINATION. H. FOR DOOR TYPES AND SIZES, SEE DETAIL SHEET -. NOTE: ALL DOORS

PER DOOR SCHEDULE ARE FINISH OPENINGS. I. CONTRACTOR TO PROTECT AND KEEP THE FLOOR SLAB CLEAN. ALL EQUIPMENT

TO BE DIAPERED INCLUDING CARS AND TRUCKS. J. ALL EXIT MAN DOORS IN WAREHOUSE TO HAVE ILLUMINATED EXIT SIGN.

HARDWARE.

K. HIGHLY FLAMMABLE AND COMBUSTIBLE MATERIAL SHALL NOT BE USED OR STORED IN THIS BUILDING.

EACH EXTERIOR EXIT DOOR SHALL BE IDENTIFIED BY A TACTILE EXIT SIGN WITH THE WORDS "EXIT". THE MOUNTING HEIGHT FOR SUCH SIGNAGE SHALL BE 60" FROM FINISH FLOOR LEVEL TO THE CENTER OF THE SIGN.

M. NON-ACCESSIBLE DOOR. PROVIDE WARNING SIGN LOCATED IN THE INTERIOR SIDE PER CBC 1133B.1.1.1

N. ALL ROOF MOUNTED MATERIALS SHALL BE FULLY SCREENED FROM PUBLIC VIEW, SEE A/A4.1 OFFICE SECTION.

FLOOR SLAB AND POUR STRIPS REQ.

THESE NOTES ARE VERY MIN. REQUIREMENT. SEE "S" DWGS FOR ADDITIONAL REQUIREMENTS

1. FLOOR COMPACTION - 95% 2. TRENCH COMPACTION - 90%

3. BUILDING FLOOR SLAB: A. 6" THICK MIN. UNREINFORCED CONCRETE OVER COMPACTED SOILS

B. 3/4" - 16"LONG @ 12" O.C. DOWELS AT ALL CONSTRUCTION JOINTS

3/4" - 16"LONG @ 24" O.C. DOWELS IN DOWEL BASKET AT ALL CONTROL JOINTS. C. 4,000 P.S.I. REQUIREMENT.

D. SLUMP TO BE 4" +/- 1"

E. JOINT SPACING PER A.C.I. 302-IR-96

F. SAW-CUT DEPTH 1/4 T; SOFT SAW-CUTTING WITHIN 2 HRS OF FINISHING 4. CONTRACTOR TO BUILD FOR CLASS V FLOOR PER A.C.I. 302-IR-96

5. CONCRETE SLAB TO HAVE STEEL FLOAT HARD TROWEL BURNISHED FINISH.

6. CONTRACTOR TO CURE SLAB TO BE WET CURING USING BURLINE FOR 7 DAYS MIN.

7. ALL EQUIPMENT & MOVING VEHICLES SHALL BE DIAPERED.

8. NO CRANES, CONCRETE TRUCKS, OR ANYTHING HEAVIER WILL BE PLACED ON THE SLAB.

9. SLAB TO BE FF50 FL35 MEASURED WITHIN 24 HOURS. 10. NO FLY ASH IN THE CONCRETE

INDICATED, PROVIDE VAPOR BARRIER (15MIL STEGO OR EQUAL) UNDER THE CONCRETE SLAB. PROVIDE SAND PER SOILS ENGINEER OR MANUFACTURER'S RECOMMENDATION.

CONCRETE SLAB IN FUTURE OFFICE AREAS, WHERE SAND OVER VIQUEEN ARE REQUIRED, SHALL BE NATURALLY HYDRATED WITHOUT USE OF BURLENE, CURING COMPOUND, OR RELEASE AGENTS.

CONTROL/CONSTRUCTION JOINTS SHALL NOT BE FILLED WITH MM-80 JOINT FILLER

IN FUTURE OFFICE AREAS. 12. SEAL CONCRETE SLAB W/ "LIPIDOLITH" SEALER



hpa, inc 18831 bardeen avenue - ste. #100 irvine, ca tel: 949 •863 •1770 fax: 949 · 863 · 0851 email: hpa@hparchs.com



GRIFFCO LAND

2518 N. SANTIAGO BLVD. ORANGE, CA 92867 TEL: 714-998-3400



2518 N. SANTIAGO BLVD. ORANGE, CA 92867 TEL: 714-998-3400



TEMESCAL CANYON FACILITY

CORONA 92883, CA



THE KAHLEN GROUP Structural: Mechanical Plumbing: Electrical: Landscape:

Fire Protection:

Soils Engineer:

overall floor pla

16084 Project Number Drawn by: 04/13/16 Date:

Revision: 07/12/16 2ND SUBMITTAL

Sheet: