
EXHIBIT B



<u>WASTEWATER TREATMENT PLANT I GENERAL MAP</u> SCALE: 1" - 200"

CONSTRUCTION NOTES

- SCHEDULE A EXISTING 8-INCH STEEL WATER INSTALL NEW 8 DUCTILE IRON PIPE INSIDE IG STEEL CASING, AND (2) NEW 8-INCH DOUBLE BALL FLEX-TEND CONNECTORS PER DETAILS ON DRAWING C-2
- SCHEDULE B EXISTING 4-INCH SEWER FORCEMAIN RELOCATE PER DRAWING C-3 BY INSTALLING 4-INCH HDPE PIPE INSIDE EXISTING 12-INCH PVC PIPE TO BE ABANDONED (SCHEDULE D).
- SCHEDULE C EXISTING 4-INCH WATER TO BE ABANDONED AND CAPPED PER DRAWING C-3.
- SCHEDULE D EXISTING 12-INCH PVC RECYCLED WATER RELOCATE BY INSTALLING 14-INCH HDPE PIPE INSIDE THE ABANDONED 24-INCH EFFLUENT (SCHEDULE E). SEE DRAWING C-4 FOR DETAILS.
- SCHEDULE E EXISTING ABANDONED 24-INCH EFFLUENT TO BE USED AS CASING PER DRAWING C-4.
- SCHEDULE F EXISTING 24-INCH EFFLUENT INSTALL (2) 24-INCH DOUBLE BALL FLEX-TEND CONNECTORS. SEE DRAWING C-4 FOR DETAILS.
- SCHEDULE G EXISTING 42-INCH RCP TREATED SEWER INSTALL (2) 42-INCH REDFLEX SLIP-ON SERIES SL-53 TRIPLE ARCH EXPANSION JOINTS, REPLACE 80-FEET OF RCP PIPE W/CML&C STEEL PIPE AND CONCRETE ENCASEMENT. SEE DRAWING C-5 FOR DETAILS.
- SCHEDULE H EXISTING 12-INCH C-900 PVC WATER REPLACE WITH 12-INCH DUCTILE IRON PIPE, 20 CASING , AND (2) NEW DOUBLE BALL FLEX-TEND CONNECTORS PER DRAWING C-6.
- SCHEDULE I EXISTING 18-INCH VCP SEWER REPLACE WITH CONTINUOUSLY WELDED 18-INCH HDPE BETWEEN MANHOLES PER PLAN AND PROFILE ON DRAWING C-7.
- SCHEDULE J EXISTING 12-INCH STEEL WATER RELOCATE TO AUBURNDALE STREET PER DRAWINGS C-8 THROUGH C-12. ABANDON EXISTING PIPELINE, REMOVE EXISTING VALVES AT BOTH ENDS WHERE INDICATED AND INSTALL BLIND FLANGES.

AKM JOB No. 0760774.10

Call: TOLL FREE

422-4133

1-800

Underground Service Alert

IWO WORKING DAYS BEFORE YOU DIG






SCHEDULE H

Assistant General Manager Department of Water and Power

CITY OF CORONA - PRADO DAM UTILITY RELOCATION C-1 GENERAL MAPS

REMOVE EXISTING VALVE AND BLIND FLANGE



N:\0760 Corona\774 Prado Dam Utility Relocation\03_C-1_index map.dgn 2/28/200

Exp. 3/31/07