



Agenda Report

File #: 18-2087

**AGENDA REPORT
REQUEST FOR CITY COUNCIL ACTION**

DATE: 9/19/2018

TO: Honorable Mayor and City Council Members

FROM: Community Development Department

SUBJECT:

City Council consideration to approve CUP2018-0007 for a 2,000 square foot drive-through car wash associated with a convenience store and fueling station (located at the northwest corner of Dos Lagos Drive and Temescal Canyon Road) in the Commercial designation of the Dos Lagos Specific Plan. (Applicant: Terrano Plaza, LLC - Rexco)

RECOMMENDED ACTION:

That the City Council

1. Take no action, thereby affirming the Planning and Housing Commission's action granting CUP2018-0007, based on the findings contained in the staff report and conditions of approval.

OR

2. Set the item for review at a subsequent meeting.

ANALYSIS:

The Dos Lagos Specific Plan (SP-99-03) establishes the land uses that are permitted in the various designations. In the Commercial designation, *Automobile car wash, detailing* is listed as permitted with a Conditional Use Permit. The proposed car wash will be an ancillary use to the convenience store/fuel station evaluated under PP2018-0003 for the greater commercial center at the northwest corner of Dos Lagos Drive and Temescal Canyon Road. This facility will be structurally part of the convenience store building which is located at the southernmost portion of the overall commercial site. The car wash will be situated along the southerly elevation. The building backs up to the corner of the site with the fuel pumps, parking and circulation on the interior which is a requirement under

the municipal code intended to ensure aesthetic treatment of these types of establishments. Entry into the car wash drive is shown west of the building with the circulation pattern counter-clockwise from plan view, exiting at the east side of the building. The required setbacks for the building and drive lane are 15 feet from each property line along the adjacent street frontages.

The operations will be designed as a self-serve drive-through format with fully automated equipment on the interior of the wash tunnel. It is anticipated that the convenience store will have 24-hour operations; however, the applicant has expressed that the car wash will be operational from 6:00 a.m. to 10:00 p.m. Operational noise is expected to be minimal as the equipment is contained within the 2,000 square foot wash tunnel.

The south building elevation will have visibility along Dos Lagos Drive. The car wash is attached to the convenience store and will carry the same architecture as the primary building. The equipment and electrical rooms are in the intervening building space between the store and the car wash tunnel.

The municipal code requires self-service car washes to have at least one stacking space before the tunnel and two parking spaces which the site plan demonstrates with even more stacking space if needed. The car wash in conjunction with the convenience store and fuel pumps requires 34 parking spaces and the minimum parking spaces are being provided in addition to excess parking spaces available within the commercial center. The commercial center will have reciprocal access and parking among the site for shared use among the tenants. The entire center required 278 parking spaces and 293 spaces are being provided.

Site landscaping and signage associated with the drive-through car wash was included in the overall commercial proposal reviewed as PP2018-0003 in conjunction with CUP2018-0007. The CUP is simply for the establishment of a drive-through car wash, which is one component of the automobile service station and overall commercial proposal covering 7.3 acres.

The use is permitted by the Dos Lagos Specific Plan with a conditional use permit and meets the development standards that apply to this type of use. The actual car wash tunnel, being ancillary to the structure of the convenience store/fuel station, has been designed in a manner that blends nicely with the contemporary architecture of the main building. The proposal is consistent with General Plan goals and policies that encourage commercial development that will serve the mixed-use Planning Area as well as the nearby and passing public along the adjacent arterial roadways. The proposal is also consistent with General Plan policies that promote the upgrade of a vacant piece of land with viable commercial uses including the proposed car wash.

COMMITTEE ACTION:

The Infrastructure Committee at its meeting on May 8, 2018, reviewed the overall project and had no objections.

STRATEGIC PLAN:

Not applicable.

FISCAL IMPACT:

The applicant has paid all the required application processing fees.

ENVIRONMENTAL ANALYSIS:

Per Section 15070 of the State Guidelines for Implementing the California Environmental Quality Act (CEQA) and Section 6.02 of the City's Local Guidelines, a mitigated negative declaration was prepared for the project because the initial study showed that there is no substantial evidence in light of the whole record before the City that the project may have a significant effect on the environment. Therefore, a mitigation negative declaration is recommended for adoption.

PLANNING AND HOUSING COMMISSION ACTION:

At its meeting of August 20, 2018, the Planning and Housing Commission considered the subject matter and took the following action:

Motion was made, seconded (Rusigno/Carrillo) and carried unanimously with Commissioner Dunn absent, that the Planning and Housing Commission adopt the Mitigated Negative Declaration and Mitigation Monitoring Plan and Resolution No. 2515 granting CUP2018-0007, based on the findings contained in the staff report and conditions of approval. The minutes of the Planning and Housing Commission meeting are included as Exhibit 4.

PREPARED BY: JOANNE COLETTA, COMMUNITY DEVELOPMENT DIRECTOR

REVIEWED BY: KERRY D. EDEN, ASSISTANT CITY MANAGER/ADMINISTRATIVE SERVICES DIRECTOR

REVIEWED BY: MICHELE NISSEN, ASSISTANT CITY MANAGER

SUBMITTED BY: DARRELL TALBERT, CITY MANAGER


EXHIBITS

1. Locational and Zoning Map.
2. Overall Site Plan and Focused Site Plan for CUP2018-0007.
3. Planning and Housing Commission Staff Report.
4. Draft Minutes of the Planning and Housing Commission meeting of August 20, 2018.

APPLICANT INFORMATION

Name: Terrano Plaza, LLC, 2518 N. Santiago, Orange

LOCATIONAL & ZONING MAP



ZONING LEGEND:

- RR: Resort Residential Designation within the Dos Lagos Specific Plan (SP99-03)
- EC: Entertainment Commercial Designation within the Dos Lagos Specific Plan (SP99-03)
- C: Commercial Designation within the Dos Lagos Specific Plan (SP99-03)
- G: Golf Designation within the Dos Lagos Specific Plan (SP99-03)



Date: 07/11/2018

CUP2018-0007



EXHIBIT

SITE PLAN NOTES

- 1

2

3

4

5

6

7

8

9

10
- OPEN PARKING STALL - 9' X 20' TYPICAL

OPEN SPACE

ACCESSIBLE PARKING

PROPERTY LINE

ENTRY MONUMENT

1 CAR GARAGE (10' X 20')

2 CAR GARAGE (20' X 20')

TRASH ENCLOSURE

TRASH PICK-UP LOCATION

GATE WITH KNOX BOX
- 11

12

13

14

15

16

17

18

19

20

21
- EASEMENT

REC AND LEASING AREA

POOL

TOT LOT

SPORT COURTS

COMMERCIAL TBD

COMMERCIAL PLAZA

COMMERCIAL LOADING (12' W X 25' L)

20' WIDE STORM DRAIN EASEMENT

PARALLEL PARKING STALL - 10' X 25'

AIR/VACUUM STALL


LEGEND

- ACCESSIBLE STALL

BICYCLE PARKING

10'X10' CORNER CUT-OFF
-

NOTE: ALL PATHS SHALL BE ACCESSIBLE



PARKING SUMMARY:

RESIDENTIAL

RESIDENT PARKING	RATIO	REQUIRED	PROVIDED
BEDROOMS:			
1B - 120 DU	1.5 SP/DU	= 180 SP	
2B - 138 DU	2.0 SP/DU	= 276 SP	
3B - 18 DU	2.5 SP/DU	= 45 SP	
TOTAL RESIDENT PARKING		= 501 SP	= 432 SP GARAGE = 69 SP OPEN
GUEST PARKING	.2 SP/DU	= 56 SP	= 90 SP
TOTAL RESIDENTIAL		= 557 SP	= 591 SP

COMMERCIAL

BUILDING (USE)	AREA	RATIO	REQUIRED	PROVIDED
NORTH				
HOTEL (101 KEY)	64,065 SF	101 KEYS (1:1+2 MGR)	= 103 SP	= 103 SP
BUILDING B (RESTAURANT)	5,000 SF	(.01)	= 50 SP	= 50 SP
BUILDING C (RETAIL)	4,000 SF	(.005)	= 20 SP	= 20 SP
SHARED STREET SPACES NORTH				= 15 SP
TOTAL NORTH COMMERCIAL	73,065 SF		= 173 SP	= 188 SP
SOUTH				
BUILDING A				
RESTAURANT	3,500 SF	(.01)	= 35 SP	= 30 SP
RETAIL	2,600 SF	(.005)	= 13 SP	= 11 SP
BUILDING D (RESTAURANT)	2,500 SF	(.01)	= 25 SP	= 19 SP
GAS STATION	7,200 SF	(.004)	= 29 SP	= 29 SP
CARWASH	2,000 SF	(.01)	= 2 SP	= 2 SP
SHARED STREET SPACES SOUTH				= 14 SP
TOTAL SOUTH COMMERCIAL	17,800 SF		= 104 SP	= 105 SP
TOTAL COMMERCIAL	90,865 SF		= 277 SP	= 293 SP

TERRANO

REXCO DEVELOPMENT
2518 NORTH SANTIAGO BLVD.
ORANGE, CA. 92867
951.898.1502

PA-1

JULY 20, 2018
SCALE: 0 40 80 120

CONCEPTUAL SITE PLAN



5256 S. Mission Road, Ste 404
Bonsall, CA 92003
760.724.1198 summaarch.com

A-SP

EXHIBIT 2

New Development of Beyond Food Mart with 10 MPD and Carwash

NWC OR TEMESCAL CANYON DR. & DOS LAGO DR. CORONA, CA

Sheet Index

- A1.01 SITE PLAN
- A2.01 FLOOR PLAN
- A2.02 CANOPY PLAN & ELEVATIONS
- A3.01 ELEVATIONS (EAST & WEST)
- A3.02 ELEVATIONS (NORTH & SOUTH)

Project Directory


OWNER:
SATER BROS
4300 EDISON AVE.,
CHINO, CA 91710
TEL: (909) 465-4101
FAX: (909) 606-6839

ARCHITECT & CIVIL ENGINEER:
WINSTON LIU, P.E.
TOM LAU, A.I.A.
W&W LAND DESIGN CONSULTANTS
2335 W. FOOTHILL BLVD., SUITE 1,
UPLAND, CA 91786
TEL: (909) 608-7118
FAX: (909) 948-1137

Legal Description

Vicinity Map

NOT TO SCALE



Reference Notes


- 1 PROPERTY LINES
- 2 (E) RIGHT OF WAY
- 3 (N) RIGHT OF WAY
- 4 (E) SEWER EASEMENT
- 5 (N) CURB AND GUTTER
- 6 (E) CONCRETE CURB & GUTTER
- 7 (E) CONC. SIDEWALK
- 8 (N) 38'X140' CANOPY
- 9 (N) UNDER GROUND STORAGE TANKS
- 10 (N) LANDSCAPE
- 11 (N) HEALY TANK
- 12 (N) TRANSFORMER PAD
- 13 (N) TRASH ENCLOSURE
- 14 (N) LOADING/UNLOADING
- 15 (N) MONU. SIGN
- 16 (N) HCP PARKING
- 17 (N) HCP RAMP
- 18 (N) VACUUM @ 8 LOCS.
- 19 (N) HCP PATH OF TRAVEL PER CODE STD.
- 20 (N) CONC. SIDEWALK
- 21 (E) ADJ. FENCE/RETAINING WALLS
- 22 (N) SPLITFACE CMU FENCE WALL (SEE PLAN FOR WALL HEIGHT)
- 23 NOT USED
- 24 (N) BIKE RACK PER CITY'S STD.
- 25 (N) ZERO EMISSION VEHICLE PARKING PER CITY'S STD.

Scope Of Work

NEW CONSTRUCTION OF A SERVICE STATION WITH CANOPY (5,325 S.F.), UNDERGROUND STORAGE TANKS, A C-STORE (7,256 S.F.) AND A CARWASH TUNNEL (1,324 S.F.)

Project Data

PROJECT ADDRESS	NWC OR TEMESCAL CANYON DR. & DOS LAGO DR. CORONA, CA
APN#	
ZONING	C-2 GENERAL COMMERCIAL
BUILDING TYPE	V-A
OCCUPANCY	A2, B & M
LOT SIZE (GROSS)	51,476 SF ± (1.18 ACRES)
BUILDING AREA:	
C-STORE	7,256 SF
CARWASH TUNNEL (INCL. ELEC/EQUIP ROOM)	1,324 SF
TOTAL AREA:	8,580 SF
CANOPY	5,325 SF
HEIGHT OF BUILDING	29'-0" (APPROX.)
SETBACK REQUIREMENTS	
FRONT YARD	10'-0"
INTERIOR SIDE	NONE
FROM ALLEY OR STREET	10'-0"
SETBACK FROM RESIDENTIAL	30'-0"
PARKING REQUIRED:	
MARKET 1/200	36
7256/200=36.28	
CARWASH TUNNEL 1/300	05
1324/300=4.41	
TOTAL REQUIRED:	41
PARKING PROVIDED:	43 (INCL. 2 HCP PARKING) (PLUS 20 UNDER THE CANOPY) +1 LOADING/UNLOADING
COVERAGE:	
(7,256+1,324)/51,476 =	16.67%
LANDSCAPE AREA	7,075 SF (±13.74%)



W&W LAND DESIGN CONSULTANTS INC.
ARCHITECTURE, CIVIL ENGINEERING & INTERIOR

2335 W. FOOTHILL BLVD., STE 1, UPLAND, CA 91786
PHONE: (909) 608-7118 FAX: (909) 948-1137

PROJECT: NEW GAS STATION, C-STORE & CARWASH TUNNEL
ADDRESS: TEMESCAL CANYON DR., CORONA, CA 92883
CLIENT: SATER BROS 4300 EDISON AVE., CHINO, CA 91710

PROJECT DIRECTORY & DATA, LEGAL DESCRIPTION, SHEET INDEX, VICINITY MAP, NOTES & SCOPE OF WORK

KEY MAP SEAL/STAMP

JOB NO. _____
DRAWN BY: _____ TL
SUPERVISED BY: _____ TL
CHECKED BY: _____ TL
PLAN CHECK _____
PERMIT SET _____
BID SET _____

REVISIONS
△ _____
△ _____
△ _____
△ _____
△ _____
△ _____
△ _____
△ _____
△ _____
△ _____

SHEET NO.

A 1.01
OF SHEETS
S H E E T



City of Corona

400 S. Vicentia Ave.
Corona, CA 92882

Agenda Report

File #: 18-2033

PLANNING AND HOUSING COMMISSION STAFF REPORT

DATE: 8/20/2018
TO: Honorable Chair and Commissioners
FROM: Community Development Department

APPLICATION REQUEST:

CUP2018-0007: Conditional Use Permit for a 2,000 square foot drive-through car wash to be located on the south side of a convenience store as part of a commercial development proposed at the northwest corner of Dos Lagos Drive and Temescal Canyon Road in the Commercial designation of the Dos Lagos Specific Plan (SP-99-03) (Applicant: Terrano Plaza, LLC - Rexco).

RECOMMENDED ACTION:

That the Planning and Housing Commission recommend adoption of the Mitigated Negative Declaration and Mitigation Monitoring Plan and Resolution No. 2515 GRANTING CUP2018-0007, based on the findings contained in the staff report and conditions of approval.

PROJECT SITE SUMMARY

Area of Property: Approximately 1.5 acres
Existing Zoning: C (Commercial) designation of Dos Lagos Specific Plan
Existing General Plan: MUI (Mixed Use Commercial/Residential)
Existing Land Use: Vacant
Proposed Land Use: Drive-through car wash ancillary to convenience store and fueling station within a commercial project (PP2018-0003)
Surrounding Land Uses:
N: Proposed Terrano Plaza Retail Project
E: Apartments
S: Commercial development in unincorporated County of Riverside
W: Apartments

BACKGROUND

The proposed car wash is part of an overall commercial project in Planning Area 1 of the Dos Lagos Specific Plan located at the northwest corner of Dos Lagos Drive and Temescal Canyon Road. The specific plan was amended in 2012 to provide for Planning Area 1 to have the potential to flexibly accommodate a mix of residential development with commercial development as a cohesive mixed-

use project in either a vertical or horizontal site configuration (SPA12-004). Subsequently, the entitlement for 276 apartment units was approved in 2016 for the westerly 13.7 acres under CUP16-002 along with a subdivision map (PM37070). At that time, the concept for the future commercial component on the easterly 7.3 acres of Planning Area 1 had not yet been established. The commercial concept has since further evolved with potential users and will constitute the completion of the mixed-use vision for Planning Area 1. The overall concept including the convenience store/fueling station with car wash was presented to the Infrastructure Committee at its meeting of May 2, 2018, and the Committee expressed no objection to the project design.

PROJECT DESCRIPTION

The Dos Lagos Specific Plan (SP-99-03) establishes the land uses that are permitted in the various designations. In the Commercial designation, *Automobile car wash, detailing* is listed as permitted with a Conditional Use Permit. The proposed car wash will be an ancillary use to the convenience store/fuel station that is evaluated under PP2018-0003 for the greater commercial center at the northwest corner of Dos Lagos Drive and Temescal Canyon Road. This facility will be structurally part of the convenience store building which is located at the southernmost portion of the overall commercial site. The car wash will be situated along the southerly elevation. Exhibit A illustrates the focused site plan for the convenience store/fuel station and car wash. The building backs up to the corner of the site with the fuel pumps, parking and circulation on the interior which is a requirement under the municipal code intended to ensure aesthetic treatment of these types of establishments. Entry into the car wash drive is shown west of the building with the circulation pattern counter-clockwise from plan view, exiting at the east side of the building. The required setbacks for the building and drive lane are 15 feet from each property line along the adjacent street frontages. Although demonstrated as compliant on the associated precise plan, the conditions of approval require that all drawings and project data summaries accurately demonstrate and state the required setbacks.

The operations will be designed as a self-serve drive-through format with fully automated equipment on the interior of the wash tunnel. It is anticipated that the convenience store will have 24-hour operations; however, the applicant has expressed that the car wash will be operational from 6:00 a.m. to 10:00 p.m. Operational noise is expected to be minimal as the equipment is contained within the 2,000 square foot wash tunnel.

Exhibit C-1 illustrates the south building elevation which will have visibility along Dos Lagos Drive. The exhibit also includes a depiction of the north elevation of the convenience store which is evaluated under the companion precise plan. Exhibit C-2 illustrates the appearance of the car wash tunnel from the west elevation (view from the apartment phase of Planning Area 1) and east elevation (view from Temescal Canyon Road).

The floor plan for the tunnel is shown in Exhibit D along with the interior of the convenience store branded as a food mart. The equipment and electrical rooms are in the intervening building space between the store and the car wash tunnel.

The municipal code requires self-service car washes to have at least one stacking space before the tunnel and two parking spaces which the site plan demonstrates with even more stacking space if needed. The site plan for the overall center in PP2018-0003 includes tabulations that illustrate that the convenience store/fuel station and car wash are all accommodated with the required parking contained on what can be its own parcel in the future. Although the applicant's letter states that the

stalls for drying/vacuuming will be non-exclusive for these functions, the conditions of approval require the two spaces to be marked for this use exclusively so that the patrons utilizing the car wash will know of the spaces and not obstruct site circulation by parking in drive aisles to perform any exterior work on their cars. The conditions of approval also require that any canopy installation to benefit car wash patrons must be limited to the two dedicated spaces, must reflect the architectural design of the main building, and be subject to the review and approval of the Community Development Director.

Site landscaping and signage associated with the drive-through car wash was included in the overall commercial proposal reviewed as PP2018-0003. The CUP is simply for the establishment of a drive-through car wash, which is one component of the automobile service station and overall commercial proposal covering 7.3 acres.

ENVIRONMENTAL ANALYSIS

Per Section 15070 of the State Guidelines for Implementing the California Environmental Quality Act (CEQA) and Section 6.02 of the City's Local Guidelines, a mitigated negative declaration was prepared for the project because the initial study showed that there is no substantial evidence in light of the whole record before the City that the project may have a significant effect on the environment. Therefore, a mitigation negative declaration is recommended for adoption (Exhibit F).

FISCAL IMPACT

The applicant has paid all the required application processing fees.

PUBLIC NOTICE AND COMMENTS

A 20-day public notice was mailed to all property owners within a 500-foot radius of the project site, as well as advertised in *The Sentinel Weekly News* and posted at the project site. As of the preparation of this report one letter of support for the overall commercial project was received and appended to the report for PP2018-0003.

STAFF ANALYSIS

The proposed car wash has been designed to fit cohesively within the commercial center proposed under the companion application of PP2018-0003. The use is permitted by the Dos Lagos Specific Plan with a conditional use permit and meets the development standards that apply to this type of use. The actual car wash tunnel, being ancillary to the structure of the convenience store/fuel station, has been designed in a manner that blends nicely with the contemporary architecture of the main building. More than sufficient stacking space has been designed with the drive-through lane that encircles the building. Parking has been demonstrated to be sufficient within the overall commercial center evaluated under the precise plan, and as conditioned, will appropriately serve the car wash use with the requisite two spaces designed in conjunction with other on-site parking spaces. Site development standards prescribed through the specific plan are being met by the car wash and the overall commercial project. Sufficient demonstration of the prescribed setbacks is required for all subsequent submittals by the conditions of approval.

The use is compatible with the both the residential and commercial components of the development proposed for Planning Area 1. The car wash operations will be fully contained within the tunnel which

is part of the building structure. Furthermore, the hours of operation are intended to be 6:00 a.m. to 10:00 p.m. further reducing any potential for disruption during sensitive night time hours. The proposal is consistent with General Plan goals and policies that encourage commercial development that will serve the mixed-use Planning Area as well as the nearby and passing public along the adjacent arterial roadways. The proposal is also consistent with General Plan policies that promote the upgrade of a vacant piece of land with viable commercial uses including the proposed car wash. Therefore, CUP2018-0007 is recommended for approval as conditioned.

FINDINGS OF APPROVAL FOR CUP2018-0007

1. An initial study (environmental assessment) has been prepared by the City of Corona so as to evaluate the potential for adverse environmental impacts. The environmental assessment identifies potential significant effects on the environment, but:
 - a. *Per Section 15070 of the State Guidelines for Implementing the California Environmental Quality Act (CEQA) and Section 6.02 of the city's Local CEQA Guidelines, the Mitigated Negative Declaration prepared for the project identified that the project's potentially significant effects to the environment are capable of being mitigated to less than a significant level, and therefore, based on the project mitigation measures identified in the Mitigated Negative Declaration, there is not substantial evidence in light of the whole record before the city that the project may have significant effect on the environment.*
2. All the conditions necessary for granting a Conditional Use Permit as set forth in Section 17.92.110 of the Corona Municipal Code do exist in reference to CUP2018-0007 for the following reasons:
 - a. *The proposal will not be detrimental to the public health, safety, convenience or general welfare, and will be in harmony with the various elements and objectives of the City's General Plan because the project meets or exceeds the development standards for properties in the Commercial designation of SP-99-03 and provides adequate vehicular access.*
 - b. *The project is consistent with the Mixed Use I General Plan designation for the site and will implement several goals and policies related to commercial development including Goal 1.13 and Policies 1.13.1 and 1.4.1 outlined below.*
 - c. *The proposed use is not detrimental to other existing and permitted uses in the general area of the project site because the use is within a commercial center that is designed in accordance with the development standards prescribed by the Dos Lagos Specific Plan for commercial areas within its boundaries.*
 - d. *The project relates properly to the streets and highways as it is located in a commercial center with access from a major arterial 4-lane (Temescal Canyon Road) and secondary 4-lane (Dos Lagos Drive) both of which have been fully improved with the development of the residential phase of Planning Area 1.*
 - e. *The proposed use as conditioned complies with the development standards of the Commercial land use designation of SP-99-03 which provides for the automobile car wash use with a conditional use permit.*
3. The proposal is consistent with the General Plan for the following reasons:
 - a. *The proposed use within the overall commercial project is consistent with the Mixed Use I designation of the General Plan that applies to this site.*
 - b. *The proposed use within the overall project is consistent with General Plan Goal 1.13 encouraging vital and active districts that provide for both housing and commercial in proximity to one another and with other supportive entertainment and service land uses.*
 - c. *The proposed use within the overall project is consistent with General Plan Policy 1.13.1 promoting the development of properties for mixed use projects that integrate residential and commercial uses into a*

cohesive, mutually beneficial design.

d. The proposed use within the overall project is consistent with General Plan Policy 1.4.1 to accommodate growth and development on vacant land on the city's periphery.

4. The proposal is consistent with the Dos Lagos Specific Plan (SP-99-03) for the following reasons:

a. Per Section 4.3.7 of the specific plan, automobile car wash is a use that is listed by conditional use permit.

b. The specific plan prescribes development standards that the proposed use within the overall commercial project adheres to, as conditioned.

PREPARED BY: TERRI MANUEL, AICP, PLANNING MANAGER

SUBMITTED BY: JOANNE COLETTA, COMMUNITY DEVELOPMENT DIRECTOR

EXHIBITS

1. Resolution No. 2515
2. Locational and zoning map
3. Exhibit A - Site Plan
4. Exhibit B - Conditions of Approval
5. Exhibit C-1 - C-2 Elevations
6. Exhibit D - Floor plan
7. Exhibit E - Applicant's letter dated May 8, 2018
8. Exhibit F - Environmental Documentation with aerial exhibit

Case Planner: Terri Manuel (951) 736-2434



RESOLUTION NO. 2515

APPLICATION NUMBER: CUP2018-0007

A RESOLUTION OF THE PLANNING AND HOUSING COMMISSION OF THE CITY OF CORONA, CALIFORNIA, GRANTING A CONDITIONAL USE PERMIT FOR A 2,000 SQUARE FOOT DRIVE-THROUGH CAR WASH TO BE LOCATED ON THE SOUTH SIDE OF A CONVENIENCE STORE AS PART OF A COMMERCIAL DEVELOPMENT PROPOSED AT THE NORTHWEST CORNER OF DOS LAGOS DRIVE AND TEMESCAL CANYON ROAD IN THE COMMERCIAL DESIGNATION OF THE DOS LAGOS SPECIFIC PLAN (SP-99-03) (APPLICANT: TERRANO PLAZA, LLC - REXCO).

WHEREAS, the application to the City of Corona, California, for a conditional use permit under the provisions of Chapter 17.92, Title 17, of the Corona Municipal Code, made by Pat Tritz of Terrano Plaza, Inc. on behalf of Rexco, has been duly submitted to said City's Planning and Housing Commission for decision and granted on August 20, 2018, as required by law; and

WHEREAS, after close of said hearing, the Planning and Housing Commission by formal action, found that all the conditions necessary to grant a conditional use permit as set forth in Corona Municipal Code Section 17.92.110 do exist in reference to CUP2018-0007 based on the evidence presented to the Commission during said hearing; and

WHEREAS, at the conclusion of the hearing the Planning and Housing Commission determined there is no substantial evidence, in light of the whole record before the city, that the project may have a significant effect on the environment and adopted the Mitigated Negative Declaration and Mitigation Monitoring Plan prepared for the conditional use permit in compliance with the California Environmental Quality Act.

NOW, THEREFORE, BE IT RESOLVED by the Planning and Housing Commission of the City of Corona, California, in an adjourned regular session assembled this 20th day of August 2018 that the aforesaid application for a conditional use permit is hereby granted in accordance with

the site plan depicted in Exhibit A and subject to the attached conditions, and approved for the following reasons:

1. An initial study (environmental assessment) has been prepared by the City of Corona so as to evaluate the potential for adverse environmental impacts. The environmental assessment identifies potential significant effects on the environment, but:
 - a. *Per Section 15070 of the State Guidelines for Implementing the California Environmental Quality Act (CEQA) and Section 6.02 of the city's Local CEQA Guidelines, the Mitigated Negative Declaration prepared for the project identified that the project's potentially significant effects to the environment are capable of being mitigated to less than a significant level, and therefore, based on the project mitigation measures identified in the Mitigated Negative Declaration, there is not substantial evidence in light of the whole record before the city that the project may have significant effect on the environment.*
2. All the conditions necessary for granting a Conditional Use Permit as set forth in Section 17.92.110 of the Corona Municipal Code do exist in reference to CUP2018-0007 for the following reasons:
 - a. *The proposal will not be detrimental to the public health, safety, convenience or general welfare, and will be in harmony with the various elements and objectives of the City's General Plan because the project meets or exceeds the development standards for properties in the Commercial designation of SP-99-03 and provides adequate vehicular access.*
 - b. *The project is consistent with the Mixed Use 1 General Plan designation for the site and will implement several goals and policies related to commercial development including Goal 1.13 and Policies 1.13.1 and 1.4.1 outlined below.*
 - c. *The proposed use is not detrimental to other existing and permitted uses in the general area of the project site because the use is within a commercial center that is designed in accordance with the development standards prescribed by the Dos Lagos Specific Plan for commercial areas within its boundaries.*
 - d. *The project relates properly to the streets and highways as it is located in a commercial center with access from a major arterial 4-lane (Temescal Canyon Road) and secondary 4-lane (Dos Lagos Drive) both of which have been fully improved with the development of the residential phase of Planning Area 1.*
 - e. *The proposed use as conditioned complies with the development standards of the Commercial land use designation of SP-99-03 which provides for the automobile car wash use with a conditional use permit.*
3. The proposal is consistent with the General Plan for the following reasons:
 - a. *The proposed use within the overall commercial project is consistent with the Mixed Use 1 designation of the General Plan that applies to this site.*
 - b. *The proposed use within the overall project is consistent with General Plan Goal 1.13 encouraging vital and active districts that provide for both housing and commercial in proximity to one another and with other supportive entertainment and service land uses.*
 - c. *The proposed use within the overall project is consistent with General Plan Policy 1.13.1 promoting the development of properties for mixed use projects that integrate residential and commercial uses into a cohesive, mutually beneficial design.*
 - d. *The proposed use within the overall project is consistent with General Plan Policy 1.4.1 to accommodate growth and development on vacant land on the city's periphery.*

4. The proposal is consistent with the Dos Lagos Specific Plan (SP-99-03) for the following reasons:
 - a. *Per Section 4.3.7 of the specific plan, automobile car wash is a use that is listed by conditional use permit.*
 - b. *The specific plan prescribes development standards that the proposed use within the overall commercial project adheres to, as conditioned.*

BE IT FURTHER RESOLVED that a copy of this resolution be delivered to the City Clerk of said City and a copy thereof be sent to the applicant therefore at the address of said applicant as set forth in the application for said conditional use permit.

Adopted this 20th day of August, 2018.



Mitchell Norton, Chair
Planning and Housing Commission
City of Corona, California

ATTEST:



Rafael Torres
Secretary, Planning and Housing Commission
City of Corona, California

I, Rafael Torres, Secretary to the Planning and Housing Commission of the City of Corona, California, do hereby certify that the foregoing resolution was regularly introduced and adopted in an adjourned regular session of said Planning and Housing Commission duly called and held on the 20th day of August, 2018, and was duly passed and adopted by the following vote, to wit:

AYES: Norton, Jones, Carrillo, and Ruscigno

NOES:


ABSENT: Dunn

ABSTAINED:



Rafael Torres
Secretary, Planning and Housing Commission
City of Corona, California

LOCATIONAL & ZONING MAP



ZONING LEGEND:

- RR: Resort Residential Designation within the Dos Lagos Specific Plan (SP99-03)
- EC: Entertainment Commercial Designation within the Dos Lagos Specific Plan (SP99-03)
- C: Commercial Designation within the Dos Lagos Specific Plan (SP99-03)
- G: Golf Designation within the Dos Lagos Specific Plan (SP99-03)



Date: 07/11/2018

CUP2018-0007



New Development of Beyond Food Mart with 10 MPD and Carwash

NWC OR TEMESCAL CANYON DR. & DOS LAGO DR. CORONA, CA

Sheet Index

A1.01 SITE PLAN
A2.01 FLOOR PLAN
A2.02 CANOPY PLAN & ELEVATIONS
A3.01 ELEVATIONS (EAST & WEST)
A3.02 ELEVATIONS (NORTH & SOUTH)

Project Directory


OWNER:
SATER BROS
4300 EDISON AVE.,
CHINO, CA 91710
TEL: (909) 465-4101
FAX: (909) 606-6839

ARCHITECT & CIVIL ENGINEER:
WINSTON LIU, P.E.
TOM LAU, A.I.A.
W&W LAND DESIGN CONSULTANTS
2335 W. FOOTHILL BLVD., SUITE 1,
UPLAND, CA 91786
TEL: (909) 608-7118
FAX: (909) 948-1137

Legal Description

Vicinity Map

NOT TO SCALE



Reference Notes


- 1 PROPERTY LINES
- 2 (E) RIGHT OF WAY
- 3 (N) RIGHT OF WAY
- 4 (E) SEWER EASEMENT
- 5 (N) CURB AND GUTTER
- 6 (E) CONCRETE CURB & GUTTER
- 7 (E) CONC. SIDEWALK
- 8 (N) 38'X140' CANOPY
- 9 (N) UNDER GROUND STORAGE TANKS
- 10 (N) LANDSCAPE
- 11 (N) HEALY TANK
- 12 (N) TRANSFORMER PAD
- 13 (N) TRASH ENCLOSURE
- 14 (N) LOADING/UNLOADING
- 15 (N) MONU. SIGN
- 16 (N) HCP PARKING
- 17 (N) HCP RAMP
- 18 (N) VACUUM @ 8 LOCS.
- 19 (N) HCP PATH OF TRAVEL PER CODE STD.
- 20 (N) CONC. SIDEWALK
- 21 (E) ADJ. FENCE/RETAINING WALLS
- 22 (N) SPLITFACE CMU FENCE WALL (SEE PLAN FOR WALL HEIGHT)
- 23 NOT USED
- 24 (N) BIKE RACK PER CITY'S STD.
- 25 (N) ZERO EMISSION VEHICLE PARKING PER CITY'S STD.

Scope Of Work

NEW CONSTRUCTION OF A SERVICE STATION WITH CANOPY (5,325 S.F.), UNDERGROUND STORAGE TANKS, A C-STORE (7,256 S.F.) AND A CARWASH TUNNEL (1,324 S.F.)

Project Data

PROJECT ADDRESS	NWC OR TEMESCAL CANYON DR. & DOS LAGO DR. CORONA, CA
APN#	
ZONING	C-2 GENERAL COMMERCIAL
BUILDING TYPE	V-A
OCCUPANCY	A2, B & M
LOT SIZE (GROSS)	51,476 SF ± (1.18 ACRES)
BUILDING AREA:	
C-STORE	7,256 SF
CARWASH TUNNEL (INCL.ELEC/EQUIP ROOM)	1,324 SF
TOTAL AREA:	8,580 SF
CANOPY	5,325 SF
HEIGHT OF BUILDING	29'-0" (APPROX.)
SETBACK REQUIREMENTS	
FRONT YARD	10'-0"
INTERIOR SIDE	NONE
FROM ALLEY OR STREET	10'-0"
SETBACK FROM RESIDENTIAL	30'-0"
PARKING REQUIRED:	
MARKET 1/200	
7256/200=36.28	36
CARWASH TUNNEL 1/300	
1324/300=4.41	05
TOTAL REQUIRED:	41
PARKING PROVIDED:	43 (INCL. 2 HCP PARKING) (PLUS 20 UNDER THE CANOPY) +1 LOADING/UNLOADING
COVERAGE:	
(7,256+1,324)/51,476 =	16.67%
LANDSCAPE AREA:	7,075 SF (±13.74%)



W&W LAND DESIGN CONSULTANTS INC.
ARCHITECTURE, CIVIL ENGINEERING & INTERIOR

2335 W. FOOTHILL BLVD., STE 1, UPLAND, CA 91786
PHONE: (909) 608-7118 FAX: (909) 948-1137

PROJECT: NEW GAS STATION, C-STORE & CARWASH TUNNEL

ADDRESS: TEMESCAL CANYON RD., CORONA, CA 92883

CLIENT: SATER BROS
4300 EDISON AVE., CHINO, CA 91710

PROJECT DIRECTORY & DATA, LEGAL DESCRIPTION, SHEET INDEX, VICINITY MAP, NOTES & SCOPE OF WORK

KEY MAP SEAL/STAMP

JOB NO. _____
DRAWN BY: _____ TL
SUPERVISED BY: _____ TL
CHECKED BY: _____ TL
PLAN CHECK _____
PERMIT SET _____
BID SET _____

REVISIONS	
1	
2	
3	
4	
5	
6	
7	
8	
9	
10	

SHEET NO:

A 1.01

OF SHEETS
S H E E T



Project Conditions

City of Corona

Project Number: CUP2018-0007

Description: CUP FOR DRIVE THROUGH CAR WASH

Applied: 5/15/2018

Approved:

Site APN:

Closed:

Expired:

Status: RECEIVED

Applicant: TERRANO PLAZA LLC (REXCO)

Parent Project: DPR2018-0002

2518 BIRTH SANTIAGO BLVD. ORANGE CA, 92862

Details:

LIST OF CONDITIONS

DEPARTMENT	CONTACT
BUILDING	
<p>1. BUILDING DEPARTMENT CONDITIONS:(1) Plans need to be prepared in accordance with the applicable 2016 California Building Codes.(2) All electrical equipment and electrical fixtures located in the washing area and outside exposed to the weather, shall be listed and approved for wet locations.(3) Accessible features need to be provided as required by the 2016 California Building Code.</p> <p>(4) Submit five *5* complete sets of plans including the following - * Plot Plan * Foundation Plan * Floor Plan * Ceiling and roof framing plan * Electrical Plans (electrical service shall be underground per Corona Municipal Code Section 15.06), including size of main switch, number and size of service entrance conductors, circuit schedule and demand load. * Plumbing and sewer plan, isometric, including underground diagram, water piping diagram, sewer or septic tank location, fixture units, gas piping and vents, heating and air conditioning diagram. * Landscape and Irrigation plans; Submit four (4) complete sets detached from building plans. Landscape Maintenance District plans shall be submitted directly to the Public Works Department. Landscape plans shall be approved prior to the issuance of any Building Permits.</p>	
FIRE	
<p>1. Place Fire Department DPR comments on plans as general notes.</p> <p>2. Any revised site plan shall be submitted to the Fire Department for screen check approval prior to building plan submittal.</p> <p>3. Plans shall show a minimum drive width of 28 feet.</p> <p>4. Provide plans for two (2) all weather surface access ways to be approved by the Fire Prevention Manager and construct the access way(s) to accommodate 70,000 lbs GVW during all phases of construction.</p> <p>5. All projects shall comply with the City of Corona Fire Department Site Construction Standard. A copy of which is available at the Fire Department counter. Projects shall have approved all weather access from two (2) directions and fire hydrants providing the required fire flow tested and accepted prior to combustible construction.</p> <p>6. Provide a minimum twenty-five (25) foot inside and fifty (50) foot outside radius for access drive(s).</p> <p>7. A minimum fire flow of 3000 gpm shall be provided.</p> <p>8. Fire hydrants are to be spaced a maximum 250 feet apart.</p> <p>9. Provide Class A roofing material.</p> <p>10. Per 511 of the Corona Municipal Code, a public safety radio communication study is required. Consult with the Fire Department for specific requirements for this study.</p> <p>11. A specific address, assigned by the City of Corona, shall be provided for each building as specified by the fire department address standard which can be obtained at the fire department counter at City Hall. Address must be illuminated during all hours of darkness.</p>	



Project Conditions

City of Corona

FIRE	
<p>12. Fire extinguishers shall be provided prior to occupancy. Fire extinguishers shall bear a California State Fire Marshal's service tag; it shall be appropriately rated for the hazard; it shall be mounted so that the top of the extinguisher is no higher than five (5) feet above floor level; and shall be located such that the travel distance to an extinguisher does not exceed seventy-five (75) feet.</p> <p>13.</p> <p>14. Hazardous Materials Disclosure and Business Emergency Plan required to be submitted and approved prior to occupancy or use.</p>	
PLANNING	Terri Manuel
	<p>1. The project shall comply with all applicable requirements of the Corona Municipal Code (CMC) and ordinances and the Dos Lagos Specific Plan (SP-99-03) including the payment of all required fees.</p> <p>2. The applicant or his successor in interest shall comply with the following mitigation measures established in the Mitigated Negative Declaration prepared for CUP2018-0007 as part of PP2018-0003.</p> <p>3. To the fullest extent permitted by law, the applicant shall defend, indemnify and hold the City of Corona and its directors, officials, officers, employees, volunteers and agents free and harmless from any and all claims, demands, causes of action, proceedings, costs, expenses, liabilities, losses, damages or injuries of any kind, in law or equity, in any manner arising out of, pertaining to, or incident to any attack against or attempt to challenge, set aside, void or annul any approval, decision or other action of the City of Corona, whether such approval, decision or other action was by its City Council, Planning and Housing Commission or other board, director, official, officer, employee, volunteer or agent. To the extent that Government Code Section 66474.9 applies, the City will promptly notify the applicant of any claim, action or proceeding made known to the City to which Government Code Section 66474.9 applies and the City will fully cooperate in the defense. The Applicant's obligations hereunder shall include, without limitation, the payment of any and all damages, consultant and expert fees, and attorney's fees and other related costs and expenses. The City shall have the right to retain such legal counsel as the City deems necessary and appropriate.</p> <p>4. Nothing herein shall be construed to require City to defend any attack against or attempt to challenge, set aside, void or annul any such City approval, decision or other action. If at any time Applicant chooses not to defend (or continue to defend) any attack against or attempt to challenge, set aside, void or annul any such City approval, decision or other action, the City may choose, in its sole discretion, to defend or not defend any such action. In the event that the City decides not to defend or continue the defense, Applicant shall be obligated to reimburse City for any and all costs, fees, penalties or damages associated with dismissing the action or proceeding. If at any time both the Applicant and the City choose not to defend (or continue to defend) any action noted herein, all subject City approvals, decisions or other actions shall be null and void. The Applicant shall be required to enter into any reimbursement agreement deemed necessary by the City to effectuate the terms of this condition.</p> <p>5. The permit hereby allowed is conditional upon the privileges being utilized by the securing of the first permit thereof within two (2) years after the effective date thereof, and construction work is not begun within said time and carried on diligently to completion, this authorization shall become void, and any privilege or permit granted shall be deemed to have lapsed.</p> <p>6. The approval of CUP2018-0007 is contingent upon the approval of PP2018-0003 and is subject to all applicable conditions of approval imposed thereon.</p> <p>7. All subsequent site plans and project data summaries shall accurately reflect the minimum setbacks of 15 feet from the property lines along the adjacent street frontages.</p> <p>8. Of the parking provided on-site, two parking spaces shall be designated for car wash patrons for post-wash activities. Any canopy installed to shade the spaces shall reflect the building architecture and be subject to the review and approval of the Community Development Director.</p>




Project Conditions City of Corona

PUBLIC WORKS	Chris Horn
<p>1. The Public Works and the Departments of Water and Power, Maintenance and Parks and Landscaping Conditions of Approval for the subject application and shall be completed at no cost to any government agency. All questions regarding the intent of the conditions shall be referred to the Public Works Department Land Development Section. Should a conflict arise between City of Corona standards and design criteria and any other standards and design criteria, City of Corona standards and design criteria shall prevail.</p> <p>2. All Public Works and Department of Water and Power conditions from PP2018-0003 shall apply to this entitlement as well.</p>	

Colors & Materials


- | | | | |
|--------------------------------------|---|-------------------------|---|
| 1 CEMENT BOARD SIDING | VINTAGE WOOD, NICHHA OR EQUAL
COLOR: ESPRESSO | 9 STUCCO FINISH | COLOR: SHERWIN WILLIAMS
7037 BALANCED BEIGE-249-C2 |
| 2 ALUMINUM PERFORATED
METAL PANEL | GRAINGER OR EQUAL
16-GAUGE, ROUND HOLE SHAPE,
STAGGERED HOLE PATTERN
COLOR: SHERWIN WILLIAMS
7037 BALANCED BEIGE-249-C2 | 10 GLASS CURTAIN WALL | FROSTED GLASS |
| 3 STUCCO FINISH | COLOR: SHERWIN WILLIAMS
7005 PURE WHITE-255-C1 | 11 3/4" FRY REVEAL | COLOR: SHERWIN WILLIAMS
7005 PURE WHITE-255-C1 |
| 4 GLASS/ALUM STOREFRONT | CLEAR ANDOZIED | 12 GLASS/ALUM WINDOW | CLEAR GLASS/CLEAR ANDOZIED |
| 5 METAL COPING | COLOR: SHERWIN WILLIAMS
7005 PURE WHITE-255-C1 | 13 STUCCO FINISH | COLOR: SHERWIN WILLIAMS
7040 SMOKEHOUSE-249-C6 |
| 6 ALUMINUM PERFORATED
METAL PANEL | COLOR: SHERWIN WILLIAMS
7040 SMOKEHOUSE-249-C6 | 14 METAL DOOR AND FRAME | COLOR: SHERWIN WILLIAMS
7005 PURE WHITE-255-C1 (METALLIC) |
| 7 GLASS CURTAIN WALL | CLEAR GLASS | 15 WALL PLANTERS | HARDIE PLANK
SHERWIN WILLIAMS,
COLOR: SW7586 STOLEN KISS-275-C1 |
| 8 STEEL CHANNEL | COLOR: SHERWIN WILLIAMS
7040 SMOKEHOUSE-249-C6 | 16 WALL PLANTERS | SHERWIN WILLIAMS,
COLOR: SW7586 STOLEN KISS-275-C1 |
| | | 17 LAP SIDING | HARDIE PLANK
SHERWIN WILLIAMS,
COLOR: SW7040 SMOKEHOUSE 249-C6 |



CEMENT SIDING BOARD
NICHHA OR EQUAL
COLOR: SHADOW




SHERWIN-WILLIAMS
COLOR: SW 7005
PURE WHITE
255-C1



SHERWIN-WILLIAMS
COLOR: SW 7037
BALANCED BEIGE
249-C2



SHERWIN-WILLIAMS
COLOR: SW 7040
SMOKEHOUSE
249-C6



GRAINGER
ALUMINUM PERFORATED
METAL PANEL
COLOR: SW 7037
BALANCED BEIGE
249-C2

T.O.P. WALL
29'-0" AFF
T.O.P. WALL
27'-0" AFF
T.O.P. WALL
24'-0" AFF
T.O.P. WALL
21'-6" AFF

B.O. METAL TRELLIS
8'-0" AFF

FINISHED FLOOR

North Elevation

SCALE: 3/16" = 1'-0"

T.O.P. WALL
27'-0" AFF
T.O.P. WALL
24'-0" AFF
T.O.P. WALL
22'-0" AFF

T.O.P. WALL
17'-0" AFF

B.O. METAL TRELLIS
8'-0" AFF

FINISHED FLOOR

South Elevation

SCALE: 3/16" = 1'-0"



W&W LAND DESIGN CONSULTANTS INC.
ARCHITECTURE, CIVIL ENGINEERING & INTERIOR

2335 W. FOOTHILL BLVD., STE. 1, UPLAND, CA 91786
PHONE: (909) 508-7118 FAX: (909) 946-1137

PROJECT: NEW GAS STATION, C-STORE
& CARWASH TUNNEL
ADDRESS: TEMESCAL CANYON RD.,
CORONA, CA 92883
CLIENT: SATER BROS
4300 EDISON AVE.,
CHINO, CA 91710

SHEET TITLE:
PROPOSED ELEVATIONS
(C-STORE AND CAR WASH)

KEY MAP

SEAL/STAMP

JOB NO.
DRAWN BY: TL
SUPERVISED BY: TL
CHECKED BY: TL
PLAN CHECK: / /
PERM. SET: / /
REVISED: / / / / / /
REVISIONS
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
841
842
843
844
845
846
847
848
849
850
851
852
853
854
855
856
857
858
859
860
861
862
863
864
865
866
867
868
869
870
871
872
873
874
875
876
877
878
879
880
881
882
883
884
885
886
887
888
889
890
891
892
893
894
895
896
897
898
899
900
901
902
903
904
905
906
907
908
909
910
911
912
913
914
915
916
917
918
919
920
921
922
923
924
925
926
927
928
929
930
931
932
933
934
935
936
937
938
939
940
941
942
943
944
945
946
947
948
949
950
951
952
953
954
955
956
957
958
959
960
961
962
963
964
965
966
967
968
969
970
971
972
973
974
975
976
977
978
979
980
981
982
983
984
985
986
987
988
989
990
991
992
993
994
995
996
997
998
999
1000
1001
1002
1003
1004
1005
1006
1007
1008
1009
1010
1011
1012
1013
1014
1015
1016
1017
1018
1019
1020
1021
1022
1023
1024
1025
1026
1027
1028
1029
1030
1031
1032
1033
1034
1035
1036
1037
1038
1039
1040
1041
1042
1043
1044
1045
1046
1047
1048
1049
1050
1051
1052
1053
1054
1055
1056
1057
1058
1059
1060
1061
1062
1063
1064
1065
1066
1067
1068
1069
1070
1071
1072
1073
1074
1075
1076
1077
1078
1079
1080
1081
1082
1083
1084
1085
1086
1087
1088
1089
1090
1091
1092
1093
1094
1095
1096
1097
1098
1099
1100
1101
1102
1103
1104
1105
1106
1107
1108
1109
1110
1111
1112
1113
1114
1115
1116
1117
1118
1119
1120
1121
1122
1123
1124
1125
1126
1127
1128
1129
1130
1131
1132
1133
1134
1135
1136
1137
1138
1139
1140
1141
1142
1143
1144
1145
1146
1147
1148
1149
1150
1151
1152
1153
1154
1155
1156
1157
1158
1159
1160
1161
1162
1163
1164
1165
1166
1167
1168
1169
1170
1171
1172
1173
1174
1175
1176
1177
1178
1179
1180
1181
1182
1183
1184
1185
1186
1187
1188
1189
1190
1191
1192
1193
1194
1195
1196
1197
1198
1199
1200
1201
1202
1203
1204
1205
1206
1207
1208
1209
1210
1211
1212
1213
1214
1215
1216
1217
1218
1219
1220
1221
1222
1223
1224
1225
1226
1227
1228
1229
1230
1231
1232
1233
1234
1235
1236
1237
1238
1239
1240
1241
1242
1243
1244
1245
1246
1247
1248
1249
1250
1251
1252
1253
1254
1255
1256
1257
1258
1259
1260
1261
1262
1263
1264
1265
1266
1267
1268
1269
1270
1271
1272
1273
1274
1275
1276
1277
1278
1279
1280
1281
1282
1283
1284
1285
1286
1287
1288
1289
1290
1291
1292
1293
1294
1295
1296
1297
1298
1299
1300
1301
1302
1303
1304
1305
1306
1307
1308
1309
1310
1311
1312
1313
1314
1315
1316
1317
1318
1319
1320
1321
1322
1323
1324
1325
1326
1327
1328
1329
1330
1331
1332
1333
1334
1335
1336
1337
1338
1339
1340
1341
1342
1343
1344
1345
1346
1347
1348
1349
1350
1351
1352
1353
1354
1355
1356
1357
1358
1359
1360
1361
1362
1363
1364
1365
1366
1367
1368
1369
1370
1371
1372
1373
1374
1375
1376
1377
1378
1379
1380
1381
1382
1383
1384
1385
1386
1387
1388
1389
1390
1391
1392
1393
1394
1395
1396
1397
1398
1399
1400
1401
1402
1403
1404
1405
1406
1407
1408
1409
1410
1411
1412
1413
1414
1415
1416
1417
1418
1419
1420
1421
1422
1423
1424
1425
1426
1427
1428
1429
1430
1431
1432
1433
1434
1435
1436
1437
1438
1439
1440
1441
1442
1443
1444
1445
1446
1447
1448
1449
1450
1451
1452
1453
1454
1455
1456
1457
1458
1459
1460
1461
1462
1463
1464
1465
1466
1467
1468
1469
1470
1471
1472
1473
1474
1475
1476
1477
1478
1479
1480
1481
1482
1483
1484
1485
1486
1487
1488
1489
1490
1491
1492
1493
1494
1495
1496
1497
1498
1499
1500
1501
1502
1503
1504
1505
1506
1507
1508
1509
1510
1511
1512
1513
1514
1515
1516
1517
1518
1519
1520
1521
1522
1523
1524
1525
1526
1527
1528
1529
1530
1531
1532
1533
1534
1535
1536
1537
1538
1539
1540
1541
1542
1543
1544
1545
1546
1547
1548
1549
1550
1551
1552
1553
1554
1555
1556
1557
1558
1559
1560
1561
1562
1563
1564
1565
1566
1567
1568
1569
1570
1571
1572
1573
1574
1575
1576
1577
1578
1579
1580
1581
1582
1583
1584
1585
1586
1587
1588
1589
1590
1591
1592
1593
1594
1595
1596
1597
1598
1599
1600
1601
1602
1603
1604
1605
1606
1607
1608
1609
1610
1611
1612
1613
1614
1615
1616
1617
1618
1619
1620
1621
1622
1623
1624
1625
1626
1627
1628
1629
1630
1631
1632
1633
1634
1635
1636
1637
1638
1639
1640
1641
1642
1643
1644
1645
1646
1647
1648
1649
1650
1651
1652
1653
1654
1655
1656
1657
1658
1659
1660
1661
1662
1663
1664
1665
1666
1667
1668
1669
1670
1671
1672
1673
1674
1675
1676
1677
1678
1679
1680
1681
1682
1683
1684
1685
1686
1687
1688
1689
1690
1691
1692
1693
1694
1695
1696
1697
1698
1699
1700
1701
1702
1703
1704
1705
1706
1707
1708
1709
1710
1711
1712
1713
1714
1715
1716
1717
1718
1719
1720
1721
1722
1723
1724
1725
1726
1727
1728
1729
1730
1731
1732
1733
1734
1735
1736
1737
1738
1739
1740
1741
1742
1743
1744
1745
1746
1747
1748
1749
1750
1751
1752
1753
1754
1755
1756
1757
1758
1759
1760
1761
1762
1763
1764
1765
1766
1767
1768
1769
1770
1771
1772
1773
1774
1775
1776
1777
1778
1779
1780
1781
1782
1783
1784
1785
1786
1787
1788
1789
1790
1791
1792
1793
1794
1795
1796
1797
1798
1799
1800
1801
1802
1803
1804
1805
1806
1807
1808
1809
1810
1811
1812
1813
1814
1815
1816
1817
1818
1819
1820
1821
1822
1823
1824
1825
1826
1827
1828
1829
1830
1831
1832
1833
1834
1835
1836
1837
1838
1839
1840
1841
1842
1843
1844
1845
1846
1847
1848
1849
1850
1851

Colors & Materials

- 1

CEMENT BOARD SIDING

VINTAGE WOOD, NICHHA OR EQUAL
COLOR: ESPRESSO
- 2

ALUMINUM PERFORATED METAL PANEL

GRAINGER OR EQUAL
16-GAUGE, ROUND HOLE SHAPE,
STAGGERED HOLE PATTERN
COLOR: SHERWIN WILLIAMS
7037 BALANCED BEIGE-249-C2
- 3

STUCCO FINISH

COLOR: SHERWIN WILLIAMS
7005 PURE WHITE-255-C1
- 4

GLASS/ALUM STOREFRONT

CLEAR ANDOZIED
- 5

METAL COPING

COLOR: SHERWIN WILLIAMS
7005 PURE WHITE-255-C1
- 6

ALUMINUM PERFORATED METAL PANEL

COLOR: SHERWIN WILLIAMS
7040 SMOKEHOUSE-249-C6
- 7

GLASS CURTAIN WALL

CLEAR GLASS
- 8

STEEL CHANNEL

COLOR: SHERWIN WILLIAMS
7040 SMOKEHOUSE-249-C6
- 9

STUCCO FINISH

COLOR: SHERWIN WILLIAMS
7037 BALANCED BEIGE-249-C2
- 10

GLASS CURTAIN WALL

FROSTED GLASS
- 11

3/4" FRY REVEAL

COLOR: SHERWIN WILLIAMS
7005 PURE WHITE-255-C1
- 12

GLASS/ALUM WINDOW

CLEAR GLASS/CLEAR ANDOIZED
- 13

STUCCO FINISH

COLOR: SHERWIN WILLIAMS
7040 SMOKEHOUSE-249-C6
- 14

METAL DOOR AND FRAME

COLOR: SHERWIN WILLIAMS
7005 PURE WHITE-255-C1 (METALLIC)
- 15

WALL PLANTERS

HARDIE PLANK
SHERWIN WILLIAMS,
COLOR: SW7586 STOLEN KISS-275-C1
- 16

WALL PLANTERS


SHERWIN WILLIAMS,
COLOR: SW7586 STOLEN KISS-275-C1
- 17

LAP SIDING


HARDIE PLANK
SHERWIN WILLIAMS,
COLOR: SW7040 SMOKEHOUSE 249-C6




CEMENT SIDING BOARD
NICHHA OR EQUAL
COLOR: SHADOW



SHERWIN-WILLIAMS
COLOR: SW 7005
PURE WHITE
255-C1



SHERWIN-WILLIAMS
COLOR: SW 7037
BALANCED BEIGE
249-C2



GRAINGER
ALUMINUM PERFORATED
METAL PANEL
COLOR: SW 7037
BALANCED BEIGE
249-C2

- T.O.P. WALL

29'-0" AFF
- T.O.P. WALL

27'-0" AFF
- T.O.P. WALL

24'-0" AFF
- T.O.P. WALL

21'-6" AFF

- B.O. METAL TRELLIS

8'-0" AFF

FINISHED FLOOR

West Elevation

SCALE: 3/16" = 1'-0"

- T.O.P. WALL

27'-0" AFF
- T.O.P. WALL

24'-0" AFF
- T.O.P. WALL

22'-0" AFF

- T.O.P. WALL

17'-0" AFF

- B.O. METAL TRELLIS

8'-0" AFF

FINISHED FLOOR

8 1 9 3 13 3 10 1 4 8

East Elevation

SCALE: 3/16" = 1'-0"



W&W LAND DESIGN CONSULTANTS INC.
ARCHITECTURE, CIVIL ENGINEERING & INTERIOR

2335 W. FOOTHILL BLVD., STE 1, UPLAND, CA 91786
PHONE: (909) 608-7118 FAX: (909) 946-1137

PROJECT: NEW GAS STATION, C-STORE
& CARWASH TUNNEL

ADDRESS: TEMESCAL CANYON RD.,
CORONA, CA 92883

CLIENT: SATER BROS
4300 EDISON AVE.,
CHINO, CA 91710

PROPOSED ELEVATIONS
(C-STORE AND CAR WASH)

SHEET TITLE:

KEY MAP

SEALED/STAMP

JOB NO: _____
DRAWN BY: TL
SUPERVISED BY: TL
CHECKED BY: TL
PLAN CHECK: / /
PERMIT SET: / /
BID SET: / /


REVISIONS

1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		

SHEET NO.

A 3.02

OF SHEETS
S H E E T



SCALE: 3/16" = 1'-0"

Proposed Floor Plan



W&W LAND DESIGN CONSULTANTS INC.
ARCHITECTURE, CIVIL ENGINEERING & INTERIOR
2335 W. FOOTHILL BLVD., STE 1, UPLAND, CA 91786
PHONE: (909) 608-7118 FAX: (909) 946-1137

PROJECT: NEW GAS STATION, C-STORE & CARWASH TUNNEL

ADDRESS: TEMESCAL CANYON RD., CORONA, CA 92883

CLIENT: SATER BROS 4300 EDISON AVE., CHINO, CA 91710

SHEET TITLE: FLOOR PLAN (C-STORE AND CAR WASH)

KEY MAP SEAL/STAMP

JOB NO.	_____
DRAWN BY:	TL
SUPERVISED BY:	TL
CHECKED BY:	TL
PLAN CHECK	____/____
PERMIT SET	____/____
BID SET	____/____
REVISIONS	
△	_____
△	_____
△	_____
△	_____
△	_____
△	_____
△	_____

SHEET NO: **A 2.01**
OF SHEETS
S H E E T

ALL IDEAS, DESIGNS, ARRANGEMENTS AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY, AND THE PROPERTY OF W&W LAND DESIGN CONSULTANTS INC. AND PROTECTED BY THE COPYRIGHT, ARCHITECTURAL, ENGINEERING, INTERIOR DESIGN, AND OTHER APPROPRIATE LAWS. NO PART OF THESE DRAWINGS MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE WRITTEN PERMISSION OF W&W LAND DESIGN CONSULTANTS INC. THESE DRAWINGS ARE NOT VALID FOR CONSTRUCTION PURPOSES UNLESS EXPRESSEDLY CERTIFIED BY W&W LAND DESIGN CONSULTANTS INC. FOR CONSTRUCTION PURPOSES ONLY. COPYRIGHT © 2017 W&W LAND DESIGN CONSULTANTS

Terrano Plaza L.L.C.
2518 N. Santiago Blvd.
Orange, CA 92687
(951) 898-1502

May 8, 2018

Ms. Terri Manuel

City of Corona
Community Development Department
400 S. Vicentia Avenue
Corona, CA 92879

Re: **DPR018 - 002**
Conditional Use Permit for a Drive Through
Car Wash Located
in Dos Lagos Specific Plan Planning Area #1

Dear Ms. Manuel,

Terrano Plaza, LLC is requesting a Conditional Use Permit for the aforementioned project described as follows:

Drive Through Car Wash:

The construction of a approximately 2,000 square foot drive-through Car Wash to be located at the south side of the new 7,200 square foot convenience market on the south west corner of Dos Lagos Drive and Temescal Canyon Road.

Vehicles will enter the wash-only queuing lane in a southerly direction on the west side of the convenience store (at NWC) The Car Wash will provide queuing for four to five vehicles. The wash structure will be parallel to the convenience market allowing the vehicles to exit at the north end of the building.

The Car Wash will be fully automated with no manual washing services provided.

The proposed drying / vacuuming area will be located in the parking area of the parcel in a location not to impede the circulation of the project. The stalls for the drying / vacuuming will be used non-exclusively for these functions.

The project is located in Planning Area #1 on an approximate 1.5-acre site (the exact size of the parcel will be determined) in the Commercial district of the Dos Lagos Specific Plan (SP99-03).

Surrounding Uses:

North: Terrano Plaza Retail Project
East: Encanto Apartment Homes
South: Dos Lagos Drive
West: Terrano Apartment Homes

Site Design:

The Car Wash structure will be designed as part of the overall building design for the convenience market. The exterior architecture will be designed to ensure the car wash structure is an integral portion of the structure for the convenience market.

Architecture and Materials:

The exterior of the buildings will feature architectural reveals, architectural siding, articulation at the top and other areas of the exterior walls. There will be accent colors to enhance the exterior appearance of the building.

Parking & Access:

Project entry will be from Temescal Canyon Road. There will be adequate drive aisles and roadway access for emergency vehicles to all sides of the building

Landscaping:

Landscaping will consist of California-Friendly, low and medium water use plant material. Plants have been chosen to create a uniform theme across the site. Maintenance and longevity of plant material has been taken into consideration. Additionally, landscaping will be used to help minimize the view of the interior of the wash from the surrounding areas. All landscaped areas will conform to the current City of Corona Landscape Guidelines.

Comprehensive Sign Program:

Signage will consist of building signage in conformance with the signage standards set forth in the Dos Lagos Specific Plan pursuant to a comprehensive sign program.

The project is within the Commercial (C) zone of the Dos Lagos Specific Plan. The proposed development will contribute to the original vision of Dos Lagos as a sustainable, mixed-use environment within walking distance of the lifestyle center.

Griffco Land L.L.C. respectfully requests your consideration and approval of the proposed Permit for project. If you have any questions concerning this applications or the proposed project, please contact me at (951) 898-1502.

Terrano Plaza, LLC



Patrick Tritz



CITY OF CORONA

MITIGATED NEGATIVE DECLARATION

NAME, DESCRIPTION AND LOCATION OF PROJECT:

PP2018-0003

Application for a Precise Plan review of a proposed 90,865 square foot proposed commercial development including a four-story hotel, 11,000 square feet of restaurant space including a drive-through, 15,800 square feet of retail floor area including convenience store/10-pump fuel station with a 2,000 square foot drive through car wash (CUP2018-0007) on 7.3 acres located at the northwest corner of Dos Lagos Drive and Temescal Canyon Road in the Commercial designation of the Dos Lagos Specific Plan (SP-99-03).

CUP2018-0007

Application for a Conditional Use Permit for a 2,000 square foot drive-through car wash to be located on the south side of a proposed convenience store (PP2018-0003) as part of a commercial development proposed at the northwest corner of Dos Lagos Drive and Temescal Canyon Road in the Commercial designation of the Dos Lagos Specific Plan (SP-99-03).

ENTITY OR PERSON UNDERTAKING PROJECT:

Patrick Tritz and Griffin Hauptert, Terrano Plaza LLC (Rexco), 2518 N. Santiago Blvd., Orange, CA 92867

The Planning and Housing Commission, having reviewed the initial study of this proposed project and the written comments received prior to the public meeting of the Commission, and having heard, at a public meeting of the Commission, the comments of any and all concerned persons or entities, including the recommendation of the City's staff, does hereby find that the proposed project may have potentially significant effects on the environment, but mitigation measures or revisions in the project plans or proposals made by or agreed to by the applicant would avoid or mitigate the effects to a point where clearly no significant effects will occur. **Therefore, the Planning and Housing Commission hereby finds that the Mitigated Negative Declaration reflects its independent judgment and shall be adopted.**

The Initial Study and other materials which constitute the records of proceedings, are available at the office of the City Clerk, City of Corona City Hall, 400 South Vicentia Avenue, Corona, CA 92882.

Date: _____

Chair
City of Corona

Date filed with County Clerk: _____

CITY OF CORONA

INITIAL STUDY / ENVIRONMENTAL CHECKLIST

PROJECT TITLE:

PP2018-0003

Application for a Precise Plan review of a proposed 90,865 square foot proposed commercial development including a four-story hotel, 11,000 square feet of restaurant space including a drive-through, 15,800 square feet of retail floor area including convenience store/10-pump fuel station with a 2,000 square foot drive through car wash (CUP2018-0007) on 7.3 acres in the Commercial designation (Planning Area 1) of the Dos Lagos Specific Plan (SP-99-03).

CUP2018-0007

Application for a Conditional Use Permit for a 2,000 square foot drive-through car wash to be located on the south side of a proposed convenience store (PP2018-0003) as part of a commercial development proposed in the Commercial designation (Planning Area 1) of the Dos Lagos Specific Plan (SP-99-03).

PROJECT LOCATION:

The northwest corner of Dos Lagos Drive and Temescal Canyon Road in the Commercial designation (Planning Area 1) of the Dos Lagos Specific Plan (SP-99-03).

PROJECT PROPONENT:

Patrick Tritz and Griffin Hauptert, Terrano Plaza LLC (Rexco), 2518 N. Santiago Blvd., Orange, CA 92867

PROJECT DESCRIPTION:

PP2018-0003 and CUP2018-0007 are two components of a mixed-use project that began in 2016 with the entitlement and construction of 276 apartment units on the westerly 13.7 acres of Planning Area 1 of the Dos Lagos Specific Plan area at the southerly tip of the city. At that time, the concept for a future commercial component of the mixed-use project was envisioned for the easterly 7.31 acres of Planning Area 1 but had not yet been solidified. With the recent construction of the apartments, the potential development of the commercial portion has further evolved with entitlement now being pursued.

ENVIRONMENTAL SETTING:

Site Description: Planning Area 1 lies north of Dos Lagos Drive between Temescal Canyon Road on the east and Interstate 15 on the west. The entire site is relatively flat. The site was historically over-excavated and rough graded with the commercial project to the immediate north, *The Shoppes at Dos Lagos*, when it was developed in 2005. The subject site contains no natural vegetation or water courses that could accommodate any fish or wildlife species.

Site Surroundings: The property to the north is developed with *The Shoppes at Dos Lagos*, a commercial lifestyle center in the Entertainment Commercial (EC) designation of the Dos Lagos Specific Plan (SP99-03). The property to the east contains an apartment complex in the Rural Residential (RR) designation of the same specific plan. To the south beyond Dos Lagos Drive are existing commercial businesses in the unincorporated County of Riverside. To the west beyond Interstate 15 is vacant property also in the unincorporated county area.

GENERAL PLAN \ ZONING:

The General Plan designation for the subject site is Mixed Use I (Commercial/Residential) which accommodates the development of properties with either retail commercial and office uses or an integrated mix of commercial and residential in a vertical or horizontal configuration on the same site which in this case is all of Planning Area 1. The Commercial designation of the site is consistent with the underlying Mixed Use I General Plan designation. The existing commercial lifestyle center to the north has an underlying General Plan designation of General Commercial with which the Dos Lagos Commercial Specific Plan designation is consistent. The existing apartments to the east have a High Density Residential (HDR) designation allowing 15-36 dwelling units per acre with which the Rural Residential Specific Plan designation is consistent. The property in the unincorporated county area to the south has a county General Plan and zoning of Commercial Retail. The vacant land to the west beyond Interstate 15 has a county General Plan and zoning of Rural Estate Residential.

STAFF RECOMMENDATION:

The City's Staff, having undertaken and completed an initial study of this project in accordance with the City's "Local Guidelines for Implementing the California Environmental Quality Act (CEQA)", has concluded and recommends the following:

- ___ The proposed project could not have a significant effect on the environment. **Therefore, a NEGATIVE DECLARATION will be prepared.**
- ___ The proposed project could have a significant effect on the environment, however, the potentially significant effects have been analyzed and mitigated to below a level of significance pursuant to a previous EIR as identified in the Environmental Checklist attached. **Therefore, a NEGATIVE DECLARATION WILL BE PREPARED.**
- XX The Initial Study identified potentially significant effects on the environment but revisions in the project plans or proposals made by or agreed to by the applicant would avoid or mitigate the effects to below a level of significance. **Therefore, a MITIGATED NEGATIVE DECLARATION will be prepared.**
- ___ The proposed project may have a significant effect on the environment. **Therefore, an ENVIRONMENTAL IMPACT REPORT is required.**
- ___ The proposed project may have a significant effect on the environment, however, a previous EIR has addressed only a portion of the effects identified as described in the Environmental Checklist discussion. As there are potentially significant effects that have not been mitigated to below significant levels, a **FOCUSED EIR will be prepared to evaluate only these effects.**
- ___ There is no evidence that the proposed project will have the potential for adverse effect on fish and wildlife resources, as defined in Section 711.2 of the Fish and Game Code.

ENVIRONMENTAL FACTORS POTENTIALLY AFFECTED

The following indicates the areas of concern that have been identified as "Potentially Significant Impact" or for which mitigation measures are proposed to reduce the impact to less than significant.

- | | | |
|---|---|---|
| <input type="checkbox"/> Land Use Planning | <input type="checkbox"/> Mineral Resources | <input type="checkbox"/> Agricultural Resources |
| <input type="checkbox"/> Population and Housing | <input type="checkbox"/> Hazards / Hazardous Materials | <input type="checkbox"/> Greenhouse Gases |
| <input type="checkbox"/> Geologic Problems | <input type="checkbox"/> Noise | <input type="checkbox"/> Tribal Cultural Resources |
| <input type="checkbox"/> Hydrology and Water Quality | <input type="checkbox"/> Public Services | <input type="checkbox"/> Mandatory Findings of Significance |
| <input type="checkbox"/> Air Quality | <input type="checkbox"/> Utilities | |
| <input checked="" type="checkbox"/> Transportation / Traffic | <input type="checkbox"/> Aesthetics | |
| <input type="checkbox"/> Biological Resources | <input checked="" type="checkbox"/> Cultural Resources | |

Date Prepared: 7-31-18

Prepared By: TERRI MANUEL, AICP, PLANNING MANAGER

Contact Person: Terri Manuel

Phone: 951-736-2434

AGENCY DISTRIBUTION

(check all that apply)

- _____ Responsible Agencies
- _____ Trustee Agencies (CDFG, SLC, CDPR, UC)
- _____ State Clearinghouse (CDFG, USFWS, Redev. Projects)
- XX **SCAQMD (Includes technical studies)**
- _____ Pechanga
- XX **Soboba**
- _____ WQCB
- _____ Other _____

UTILITY DISTRIBUTION

XX **Southern California Edison**

Southern California Edison
Adriana Mendoza-Ramos, Esq.
Region Manager, Local Public
Affairs
1351 E. Francis St.
Ontario, CA 91761

Southern California Edison
Karen Cadavona
Third Party Environmental Review
2244 Walnut Grove Ave.
Quad 4C 472A

Note: This form represents an abbreviation of the complete Environmental Checklist found in the City of Corona CEQA Guidelines. Sources of reference information used to produce this checklist may be found in the City of Corona Community Development Department, 400 S. Vicentia Avenue, Corona, CA.

1. LAND USE AND PLANNING:

	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
a. Conflict with any land use plan/policy or agency regulation (general plan, specific plan, zoning)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b. Conflict with surrounding land uses	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c. Physically divide established community	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Discussion:

Planning Area 1 is part of the greater master planned area of Dos Lagos that is intended for development of a mix of land uses that include commercial, entertainment, office, and residential with internal pedestrian proximity. Planning Area 1 is identified in the master plan as a Mixed Use designation that is intended to accommodate a mix of commercial and residential uses. The 276-unit apartment complex under construction on the west side of Planning Area 1 is the residential component of the overall site development plan. The applications that are currently proposed (PP2018-0003 and CUP2018-0007) are an implementation of the commercial component of the same mixed-use project. The site development plan proposed with these applications complement the residential portion with a cohesive design that features central shared access and pedestrian proximity. The project, as a whole, as well as the separate components of multi-family residential and commercial, do not create land use incompatibilities, but rather fosters opportunities for people to live in the same area where supporting commercial, entertaining, shopping, and potentially employment are within walking distance reducing the need for vehicle trips. The project will not divide an established community because the site is an infill location master planned to fit into the context of the overall geographic area. Implementation of the project will not result in significant impacts related to land use, and therefore, no mitigation is warranted related to land use and planning.

2. POPULATION AND HOUSING:

	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
a. Induce substantial growth	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b. Displace substantial numbers of existing housing or people	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Discussion:

The proposed project does not induce substantial growth beyond that previously evaluated with the master planning of the Dos Lagos area and subsequent amendments. The specific plan provides for up to 450 residential units ascribed to Planning Area 1, and the population growth attributable to that original potential number based on the applicable factors at the time of residential entitlement (3.5 persons per household and 2.7% vacancy factor, California State Department of Finance, Demographic Research Unit, Table 2: E-5 City/County Population and Housing Estimates, 1/1/2016 *entitlement year*) the maximum potential population yield for Planning Area 1 was 1,533 persons. The residential portion was underbuilt with substantially fewer residential units (276) with a projected population yield of 940 by comparison which is within the parameters previously evaluated with SPA12-004 and GPA12-003 and within the growth parameters of the city's 2004 General Plan for build-out year 2025. The growth also was determined to not exceed the regional growth projections at the time of residential entitlement by the Southern California Association of Governments (SCAG) for the City of Corona. The proposed commercial component of this mixed-use project will not induce substantial growth or displace any housing, but rather will create a degree of sustainability by providing supportive commercial uses in pedestrian proximity of not only the residential units in Planning Area 1 but also in other parts of Dos Lagos and even in the county area to the south. Therefore, no mitigation is warranted related to population and housing.

3. GEOLOGIC PROBLEMS:

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| a. Fault /seismic failures (Alquist-Priolo zone) /Landslide/Liquefaction | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| b. Grading of more than 100 cubic yards | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| c. Grading in areas over 10% slope | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| d. Substantial erosion or loss of topsoil | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| e. Unstable soil conditions from grading | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| f. Expansive soils | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

Discussion:

Although the project site is located in a region of generally high seismicity, per Figure 4.5-7 of the General Plan Technical Background Report and the Dos Lagos Specific Plan EIR, the project site is not located within an Alquist-Priolo Seismic Special Study Zone, and no known active or potentially active fault crosses the project site. The Dos Lagos Specific Plan EIR also addressed the potential for liquefaction; however, due to the soil conditions, and combined with the relatively dense nature of the soils, the site is not subject to liquefaction. As such, this project will not result in a significant impact, and no mitigation is warranted.

The site was previously rough graded with the property to the north prior to its development with *The Shoppes at Dos Lagos* in 2005 and is relatively flat. Furthermore, Planning Area 1 was graded with the construction of the apartments on the west side of the planning area. The proposed commercial portion of the site will continue to be graded and finished a manner consistent with the overall site design that will achieve appropriate positive drainage in accordance with the city's grading regulations. Potential impacts are mitigated through adherence to the city's grading ordinances by frequent watering of the site, tire shaker plates at entrance/exits and cleaning of haul roads. Compliance with these requirements is ensured through the grading permit and inspection process through the city's Public Works Department, thereby resulting in less than significant impacts. Therefore, no mitigation is warranted related to geology.

4. HYDROLOGY AND WATER QUALITY:

	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than significant Impact	No Impact
a. Violate water quality standards/waste discharge requirements	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b. Deplete groundwater supplies	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c. Alter existing drainage pattern	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
d. Increase flooding hazard	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e. Degrade surface or ground water quality	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f. Within 100-year flood hazard area	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
g. Increase exposure to flooding	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
h. Exceed capacity of storm water drainage system	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Discussion:

The proposed development of the commercial component of Planning Area 1 will add to the impermeable surface coverage increasing surface run-off. A preliminary Water Quality Management Plan (WQMP) (Land Development Design Company, LLC, December 31, 2015) was prepared for the entirety of Planning Area 1 to ensure that the project addresses potential water quality issues. The developer will be required to implement on-site Best Management Practices (BMPs) identified in the WQMP to minimize pollutant run-off into the city's storm water drainage system. The project will implement underground storm water detention and infiltration systems on the northeast and southeast quadrants (commercial side of Planning Area 1). Such systems eliminate the need for surface holding ponds that reduce the usability of the land. Standard BMPs will also be implemented to maximize permeable surfaces, landscape with drought resistant materials reducing the need for irrigation, site maintenance, spill prevention, control and clean-up, fertilizer and pesticide management, roof run-off controls, and a host of other features that are part of the site design and ongoing operations to ensure continued water quality control. Prior to the issuance of grading permits, the applicant will be required to submit a final WQMP to be reviewed by the Public Works Department. This will result in less than significant impacts related to water quality, and therefore, no further mitigation is required.

A hydrology study was prepared as well for the full site development of Planning Area 1 (Land Development Design Company, LLC, December 31, 2015). The study evaluated the anticipated storm flows for the post-developed condition of the project site including the residential and commercial portions as they form a cohesive site development to verify the capacity of the existing storm drain at the intersection of Temescal Canyon Road and Dos Lagos Drive. Based on the project design, the site will be 80% impervious with surface flows toward the northeast into the private streets and drives where inlets will convey the flows to one of the two underground systems. Implementation of the storm water collection and conveyance systems according to the referenced hydrology study will result in less than significant impacts, and no further mitigation is required.

5. AIR QUALITY:

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

- | | | | | |
|---|--------------------------|-------------------------------------|--------------------------|-------------------------------------|
| a. Conflict with air quality plan | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| b. Violate air quality standard | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| c. Net increase of any criteria pollutant | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| d. Expose sensitive receptors to pollutants | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| e. Create objectionable odors | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

Discussion:

The project site lies within the southern portion of the South Coast Air Basin (Basin), which is a 6,600-square mile area that includes all of Orange County and the non-desert portions of Los Angeles, Riverside, and San Bernardino Counties. The agency that regulates air quality in this region is the Southern California Air Quality Management District (SCAQMD). At the state level, air quality is regulated by the California Air Resources Board (CARB) and at the federal level it is the U.S. Environmental Protection Agency (EPA). The SCAQMD is responsible for attaining state and federal clean air standards in the Basin. The SCAQMD, in coordination with the Southern California Association of Governments, is also responsible for developing, updating, and implementing the Air Quality Management Plan (AQMP) for the Basin to reduce emissions of criteria pollutants to a level that is considered safe by the CARB and EPA.

The development of Planning Area 1 was evaluated in an air quality screening assessment prepared by LDN Consulting, Inc. (January 25, 2016) with the entitlement of the 276 apartments on the westerly portion of Planning Area 1. The commercial portion of the mixed-use project was included in conceptual form at that time and was evaluated with the overall project in terms of potential air quality impacts from construction and operational emissions resulting from implementation of the project utilizing the then-latest CalEEMod air quality and greenhouse gas emissions model by ENVIRON International Corporation for the SCAQMD. Short-term emissions are those that would be related to construction including site preparation, grading, paving, building construction and architectural coatings. Operational emissions were also included with estimations for long-term during summer and winter months for energy use, mobile sources, and area sources. The 2016 study concluded that, when compared to the significance thresholds established for daily operational air quality emissions, no pollutant would exceed such thresholds on a long-term basis, and therefore, no impacts related to pollutants were identified that warranted further mitigation.

With the further refinement of the commercial portion of Planning Area 1, additional analysis has been prepared to address air quality, greenhouse gas emissions (Number 16 below) and health risk, hereinafter addressed (LDN Consulting, Inc., August 1, 2018 as revised). The mass grading of the site has been previously completed as part of the master plan and previous grading of Planning Area 1. Therefore, the only source of construction emissions for the commercial component of Planning Area 1 will be from minor site preparation, building construction, paving and architectural coating. Upon project completion, the development would generate operational emissions from daily vehicle operations, use of consumer products, and from landscaping equipment. Estimates for both construction phase and operational phase were again generated by LDN Consulting utilizing the CalEEMod calculator.

The air quality analysis was based on the worst-case scenario related to trip generation as estimated in the project traffic study (LLG, July 31, 2018, see Number 6 below) for summer and winter. Measured in pounds per day, the criteria pollutants that are analyzed for both construction and operations include Respirable Particulate Matter (PM₁₀/PM_{2.5}), Nitrogen Oxide (NO_x), Sulfur Oxide (SO_x), Carbon Monoxide (CO), and Reactive Organic Gases (ROG) (LDN Consulting, Inc., August 1, 2018, Table 1, Page 2). When compared to the significance thresholds established by the SCAQMD, no pollutant was identified as expected to exceed such thresholds for the daily construction emissions (Ibid. Table 3, page 3). Likewise, when compared to the significance thresholds established for daily operational air quality emissions, no pollutant will exceed such thresholds on a long-term basis (Ibid. Table 4, Page 4). Therefore, no impacts related to pollutants are identified that warrant further mitigation.

A Health Risk Screening Letter was also prepared by LDN Consulting, February 16, 2016 and updated June 13, 2016, which identified potential health risks in particular from toxic air contaminants (TACs) originating from Interstate 15 which lies along the western boundary of the proposed residential portion of the overall project. Health risk impacts such as elevated cancer risk can exist when sensitive receptors such as residential uses are located in proximity to sources of air pollutants that emit TACs of particular concern. Generally, risks are stated to be greater for sensitive receptors within 500 feet of a freeway or busy traffic corridor calculated based on a 70-year lifetime exposure and meteorological data. According to the study, under SCAQMD guidance, an excess cancer risk significance threshold is set at 10 in one million (LDN Consulting, Inc. [SCAQMD, 2015], Feb. 16, 2016, Page 2). The evaluation prepared by LDN utilized the latest computer modeling to estimate concentrations of particulate matter that would occur at select locations along the perimeter of the site nearest to the I-15 Freeway and to Dos Lagos Drive.

The IS/MND that was prepared for CUP16-002 entitling the 276-unit apartment complex on the westerly side of Planning Area 1 imposed mitigation measures to reduce potential health risk impacts to a level below significance. Since those measures were applicable to, and will be carried out with, the residential development of Planning Area 1, those measures are hereinafter noted for reference only. These measures remain pertinent as the commercial project under PP2018-003 includes a fueling facility with 10 pumps (20 stations) that will be in proximity of some of the apartment units in the first phase of Planning Area 1. The fueling facility is subject to regulations and separate permitting by the SCAQMD.

CUP16-002 Mitigation Measures – For Reference

- (1) *Each unit shall be installed with mechanical air quality filtration system with fresh air intake having a minimum efficiency reporting value (MERV) of 13. Such system must be clearly displayed on all plans for plan check and construction.*
- (2) *The developer shall provide written disclosure in the leasing documents for each unit that is located within 300 feet of the existing gasoline station located to the south of the project site across Dos Lagos Drive regarding the potential health risks to the residents associated with potential exposure to benzene that may be emitted from gasoline refueling operations (South Coast Air Quality Management District correspondence dated June 10, 2016, Page 2, citing Guidance for performing a gasoline dispensing station health risk assessment "Risk Assessment Procedures – Appendix X").*

6. TRANSPORTATION/TRAFFIC:

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| a. Conflict with an applicable plan, ordinance or policy establishing measures of effectiveness for the performance of the circulation system | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| b. Conflict with an applicable congestion management program | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| c. Change in air traffic patterns | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| d. Traffic hazards from design features | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| e. Emergency access | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| f. Conflict with alternative transportation policies (adopted policies, plans or programs for public transit, bicycle or pedestrian facilities) | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

Discussion:

When the Dos Lagos Specific Plan was adopted, it was accompanied by an Environmental Impact Report that identified potential impacts and mitigation measures associated with the master plan itself. The subject site was part of the evaluation but at the time was designated for commercial retail, and the traffic impacts were aggregated with the overall master plan. In 2012, when the subject site was re-designated to allow for the potential for mixed land uses that included up to 450 multi-family units in Planning Area 1, a subsequent analysis was prepared by Linscott, Law & Greenspan (July 27, 2012) to evaluate anticipated impacts to traffic and circulation based on the land use change that was proposed in 2012. The increase in residential dwelling units coupled with the decrease in commercial square footage resulted in a net decrease of daily trips for the overall Dos Lagos Specific Plan area (43,949 two-way daily trips reduced to 36,497 two-way daily trips, a net decrease of 7,452 daily trips).

The development of Planning Area 1 was further evaluated in a Traffic Impact Analysis prepared by Linscott, Law & Greenspan, Engineers (LL&G) dated December 29, 2015 and summary memo dated December 31, 2015. That analysis evaluated the construction of 276 apartments on the westerly side of Planning Area 1 and included an evaluation for a concept for the development of commercial on the easterly portion of the site, although that development plan was still being designed. The 2015 analysis compared the new project with the original specific plan and concluded at that time a reduction in daily two-way trips from the original Dos Lagos master plan (43,949) to a revised overall trip count of 39,522. While this revised count was an increase of approximately 3,000 daily two-way trips over the 2012 study because of the re-introduction of some commercial uses, that count remained *less than the original analysis* prepared for the overall Dos Lagos area as evaluated in the EIR of 2000.

The 2015 traffic study estimated the project would produce 8,801 total daily trips reduced by 3,524 trips that accounted for *internal capture* and pass-by visits for a net ADT of 5,277 (LLG Memo dated December 31, 2015). *Internal capture* is a term that characterizes reduced vehicle trips based on the proximity of uses that can foster pedestrian activity over vehicle use. The project is designed such that the residents in the area, not just in Planning Area 1, can find supportive commercial uses within walking distance. Similarly, *pass-by* credit is factored into the calculations as well, which means vehicle visits to and from the site that would already be on the adjacent roadway system and incidentally stop at the project site. Those trips do not begin or end with the project site, and therefore, can be discounted because the project does not generate those vehicles that happen to already be on the road in the area.

The 2015 traffic study for Planning Area 1 was updated by LL&G (dated May 21, 2018 and July 30, 2018 Table 5-2) to include the commercial portion now refined in its scope. The updated study calculated the *internal capture* that can be expected based on the mixed-use nature of the project and *Institute of Transportation Engineers* (ITE) Guidelines. Based on the residential unit count and floor area of all Planning Area 1 uses, average daily trips will total 9,012 minus 4,285 internal capture and pass-by trips for a net total of 4,727 average daily trips. Morning peak hour trips (entering and exiting)

are projected at 351, and evening peak hour trips (entering and exiting) are projected at 312.

It is noteworthy that internal capture and pass-by estimates are increased from the prior study because the commercial portion is now defined, whereas before, the commercial development plan was conceptual only.

The 2015 traffic study (CUP16-002 and PM 37070) evaluated ten intersections and three access points into the site from Temescal Canyon Road. The study identified one mitigation measure that was to be warranted in the Year 2018 with the residential project, and that was a signal upgrade at Temescal Canyon Road and Cajalco to provide for an eastbound right-turn overlap traffic signal phasing and restriction of northbound U-turns. What this means is that a right-turn from Temescal Canyon Road onto eastbound Cajalco would get a green arrow that will coincide with the left turn arrow on westbound Cajalco Road to southbound Temescal Canyon Road. U-turns will be restricted so as not to conflict with the green arrow movements. The 2015 traffic analysis prescribed mitigation that the developer is responsible for a 100% fair share contribution to pay for this future signal upgrade at a timing established by the Public Works Director. No other mitigation measures were warranted under those approvals.

The updated study also evaluated, in accordance with the city's scoping requirements, ten existing key study intersections in the area and four project driveways, three onto Temescal Canyon Road and one onto Dos Lagos Drive. New mitigation is recommended that supersedes the mitigation measure prescribed by the 2015 study and is expressed as follows:

Mitigation Measure:

1. Year 2020 With Project Traffic Conditions

The results of the Year 2020 With Project intersection capacity analysis presented previously in Table 8-1 indicate that the proposed Project will impact one (1) of the key study intersections. The following improvements listed below have been identified to mitigate the traffic impacts at the intersection impacted by Project traffic:

▪ **Temescal Canyon Road at Cajalco Road:** Restripe the northbound approach to provide a third exclusive northbound left-turn lane and restripe the shared northbound through/right-turn lane to an exclusive northbound right-turn lane. Install eastbound right-turn overlap traffic signal phasing and restrict northbound U-turn movements.

2. Year 2020 With Project Traffic Conditions

The developer shall be responsible for a 30.36% fair share contribution for the improvements project fair share percentage for the impacted intersection of Temescal Canyon Road at Cajalco Road. As the total cost of the improvements is estimated to be \$20,000, the Project's fair share contribution is approximately \$6,072.00.

7. BIOLOGICAL RESOURCES:

	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
a. Endangered or threatened species/habitat	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b. Riparian habitat or sensitive natural community	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c. Adversely affects federally protected wetlands	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d. Interferes with wildlife corridors or migratory species	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e. Conflicts with local biological resource policies or ordinances	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f. Conflicts with any habitat conservation plan	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Discussion:

The proposed amendment will not impact biological resources as there are no water courses or vegetation existing on the site. The project site was previously rough graded when the commercial center on the adjoining property to the north was developed in 2005. Additional grading occurred with the development of the apartment units on the west side of Planning Area 1 in 2016 and 2017. The project site and plan area were analyzed under the Dos Lagos Specific Plan EIR with all potential impacts to biological resources mitigated below a significant level. As such, no further analysis or mitigation is warranted.

The developer is required to pay applicable fees related to Riverside County's Multiple Species Habitat Conservation Plan, or MSHCP. This MSHCP is a habitat conservation plan for Western Riverside County that identifies land to be preserved for habitat for threatened, endangered or key sensitive populations of plant and wildlife species. The project site is not located within a Criteria Area, nor is the project site located within the Burrowing Owl survey area as identified in the MSHCP; therefore, the applicant is only subject to the MSHCP mitigation fee for development. This fee will be used to acquire and preserve vegetation communities and natural areas, which are known to support these sensitive species in various locations through Riverside County.

Scale broom is vegetation native to California and Arizona. It grows in sandy and gravelly soils in washes and similar alluvial environments. This species is adapted to withstand and recover from the extreme conditions caused by flooding in its native environment. Its adaptations include deep roots to anchor the plant in case of heavy scouring of the sediment substrate, and a large underground stem (or rootstock) that stores energy and enables re-sprouting if the above-ground stem is broken off or if the plant is buried as a result of flooding. Because of the energy stored in the rootstock, scale broom is able to exert tremendous pressure at the stem tip. This adaptation allows scale broom to survive under heavy sediment and may also enable it to raise or break through man-made structures under some circumstances. Therefore, prior to the issuance of any grading permit or construction of public improvements the Public Works Department requires that the developer have a qualified botanist, plant taxonomist, or field biologist (specializing in native plants) survey the site for the presence of the scale broom plant. If the plant is present on the site, the developer is required to eradicate it by means identified by the specialist, such as excavating it including the root ball with the application of herbicides. Compliance with the Public Works Department's grading permit requirements and the recommendations for removal of the plant, if applicable, will reduce the potential impacts to a less than significant level. Therefore, no additional mitigation pertaining to scale broom is required of the developer.

8. MINERAL RESOURCES:

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

- a. Loss of mineral resource or recovery site

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
--------------------------	--------------------------	--------------------------	-------------------------------------

Discussion:

Per Figure 4.5-7 of the General Plan Technical Background Report, the project site does not contain mineral resources. Therefore, the project does not impact mineral resources, and no mitigation is warranted.

9. HAZARDS AND HAZARDOUS MATERIALS:

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

- a. Transport, use or disposal of hazardous materials
- b. Risk of accidental release of hazardous materials
- c. Hazardous materials/emissions within ¼ mile of existing or proposed school
- d. Located on hazardous materials site
- e. Conflict with Airport land use plan
- f. Impair emergency response plans
- g. Increase risk of wildland fires

<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Discussion:

A Phase I Environmental Site Assessment (ESA) was prepared by Property Solutions, August 12, 2009. The assessment summarized the history of the greater Dos Lagos area which was historically a silica mine from the 1980's to 1990's. In 2003, Planning Area 1 was included as part of a mass grading operation for the Dos Lagos master plan area. Subsequently, additional grading took place in 2016 and 2017 in Planning Area 1 to accommodate the apartment project now being constructed on the westerly portion of the planning area and in anticipation of eventual development of the commercial portion on the easterly portion. The conclusions that were reported in the referenced Phase 1 ESA included the area within Planning Area 1 as well. No miscellaneous storage containers, above ground storage tanks (ASTs), underground storage tanks (USTs), vent pipes or fill pipes, septic systems or cesspools were observed on the project site. At the time of inspection, there was no unusual staining or indications of a surface release observed on the project site such as discolored soil, distressed vegetation, unusual odors, pits ponds or lagoons. No sign of hazardous material storage, generation, or usage was observed on the project site. As such, hazards or hazardous materials are not considered an impact and no mitigation is warranted.

10. NOISE:

	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
a. Exceed noise level standards	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
b. Exposure to excessive noise levels/vibrations	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
c. Permanent increase in ambient noise levels	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d. Temporary increase in ambient noise levels	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
e. Conflict with Airport Land Use Plan noise contours	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Discussion:

A noise study was prepared dated January 25, 2016 (LDN Consulting, Inc.) which addressed the residential portion of Planning Area 1 and the commercial portion in its conceptual layout. The study recommended noise attenuating measures that would benefit the more sensitive residential side of the Planning Area by requiring a six-foot high barrier along Dos Lagos Drive and the Interstate 15 on-ramp (Figure 5-2 of the LDN Study) to attenuate noise at all ground floor outdoor areas. Furthermore, dual pane windows and mechanical ventilation measures are required to attenuate noise for the residential units themselves. Those specific measures will be carried out with the construction of the residential portion (CUP16-002). No special mitigation applied in particular to the commercial portion of Planning Area 1 as it is less of a sensitive receptor.

A temporary increase in ambient noise levels is expected during the construction of the commercial project. Construction activities will result in a temporary increase in noise levels in the immediate area. The Corona Municipal Code prohibits construction noise between the hours of 8:00 p.m. to 7:00 a.m. Monday through Saturday and 6:00 p.m. to 10:00 a.m. Sundays and federal holidays. Adherence to the CMC limitations will prevent noise impacts to nearby sensitive receptors, and therefore, no special mitigation measures apply in this regard for the commercial component of Planning Area 1.

11. PUBLIC SERVICES:

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

a. Fire protection	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b. Police protection	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c. Schools	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d. Parks & recreation facilities	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e. Other public facilities or services	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Discussion:

The commercial portion of Planning Area 1 will not generate additional students to be accommodated by the Corona Norco Unified School District. The residential portion of Planning Area 1 is subject to the payment of statutory school fees at the time of building permit issuance as implemented under CUP16-002.

The development does not warrant the construction of additional public services such as fire facilities, police facilities, schools, or other similar facilities. As stipulated in the Dos Lagos Development Agreement, the developer will pay applicable development impact fees at the time of issuance of building permits for the project. Over time these fees are used by the city to fund upgrades and improvements to certain infrastructure.

12. UTILITIES:

	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
a. Exceed wastewater treatment requirements	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b. Involve construction/expansion of water or wastewater treatment facilities	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c. Involve construction/expansion of storm drains	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d. Sufficient water supplies/compliance with Urban Water Management Plan.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
e. Adequate wastewater treatment capacity	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
f. Adequate landfill capacity	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
g. Comply with solid waste regulations	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Discussion:

The City of Corona Department of Water & Power (CDWP) will provide domestic water supply to the entirety of Planning Area 1. The CDWP currently provides municipal water service to approximately 167,764 customers including residential, commercial, industrial and other land uses through approximately 640 miles of infrastructure plus 21 booster stations and 17 storage tanks. Twenty-two production wells draw from the groundwater basins providing approximately 50% of its water supply with the balance imported from the Western Municipal Water District supplied by the Colorado River and the State Water Project. The CDWP's Urban Water Management Plan (UWMP2015-2016) sets forth expected supply and demand within the service area based on land uses that have been entitled including the Dos Lagos master plan that includes Planning Area 1. Based on the draft Technical Background Report (TBR) for the city's General Plan which is currently undergoing an interim technical update, the city forecasts adequate water supplies in normal years to meet demand through 2040 (Draft General Plan TBR, June 2018, Page 3-34).

More historically, impacts to potential water resources were also evaluated under the Dos Lagos Specific Plan EIR, and the EIR found the potential impacts to be below a significant level of significance. Therefore, mitigation was not warranted. The more recent 2012 amendment which resulted in the addition of 495 residential dwellings across the Dos Lagos Specific Plan area included an evaluation for water supply. A Water Supply Assessment (WSA) was prepared (Brezack and Associates Planning, October 18, 2012) which concluded that sufficient water supplies are available to meet future demands of the service area plus the additional 495 residential dwelling units proposed for Planning Area 1 under that amendment. The evaluation factored in the city's implementation of groundwater management strategies such as groundwater recharge and increased recycled water supplies, which will serve to decrease the city's potable water supplies allowing the city to continue sustainable groundwater pumping for the city's water service area inclusive of the project site. Furthermore, the residential portion of Planning Area 1 consists of 276 apartment units, a significant underbuilding of what was entitled under the referenced 2012 amendment. The subject site had an original land use of commercial, and therefore, was included in the previous evaluations with that land use as well. Therefore, the proposed project is an implementation of the intended development of the site, and no impacts to water supply will result from the commercial development of Planning Area 1, and no mitigation is warranted.

The CDWP owns and operates wastewater treatment facilities with sufficient capacity to serve the proposed project. Specifically, the project will connect to Wastewater Treatment Plant #3, which currently treats approximately 600,000 gallons per day, but has the capacity to treat one (1) million gallons per day. Master planned infrastructure was constructed at the

time initial development of the Dos Lagos Specific Plan area occurred. The subsequent amendment that increased the overall unit count by 495 units resulted in an anticipated generation rate of approximately 185,800 gallons of additional wastewater per day, thereby bringing the total amount of wastewater treated per day to approximately 785,000 gallons, which is still within the limit of the treatment plant's overall capacity. The proposed project is within the assumed parameters for development of Planning Area 1. Therefore, the proposed project poses less than a significant impact, and no mitigation in this regard is warranted.

Southern California Edison and Southern California Gas will provide power and natural gas services to the project site. At the time of the project grading, the gas and power lines, if needed will be extended to the project site by the developer, as per other residential development throughout the city. The city's contracted waste hauler Waste Management will provide waste collection and disposal services. The amount of commercial gas, power and waste generated by the development is not expected to impact these services. AT&T will provide telephone services to the project site. The developer's coordination with AT&T will ensure timely service to the new site. Therefore, no further mitigation measures are required of the applicant.

13. AESTHETICS:	Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
a. Scenic vista or highway	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
b. Degrade visual character of site & surroundings	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
c. Light or glare	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
d. Scenic resources (forest land, historic buildings within state scenic highway)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Discussion:

The project site is not considered a scenic vista per the city's Environmental Resources Element of the General Plan. Development of the project site will be regulated by the Dos Lagos Specific Plan and the municipal code. The project's design adheres to the guidelines established for commercial development in the Dos Lagos master planned area. Varied building setbacks and landscape buffers are part of the project design for aesthetic enhancement. Furthermore, on-site lighting will be diffused and oriented in a downward manner to further mitigate the potential impacts.

14. CULTURAL RESOURCES:

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

- | | | | | |
|--|--------------------------|--------------------------|--------------------------|-------------------------------------|
| a. Historical resource | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| b. Archaeological resource | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| c. Paleontological resource or unique geologic feature | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| e. Disturb human remains | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

Discussion:

The CEQA topic related to Cultural Resources was analyzed under the Dos Lagos Specific Plan EIR for the full project area of Dos Lagos most of which contained a silica mine that was filled as part of the grading operations. A more localized analysis was prepared for Planning Area 1 along with two other potential development sites unrelated to this proposal. This analysis done by Cogstone, dated March 2016, concludes that the subject site has low potential for prehistoric or historic archaeological resources. The site was historically excavated and filled up to 14 feet and re-compacted in anticipation of future development. However, the study still prescribes that if unanticipated cultural materials are unearthed during construction, work should be halted in the area until a qualified archaeologist can assess the significance of the find. Work may resume immediately a minimum of 50 feet away from the find.

In accordance with standard mitigation required for the protection of cultural resources and in keeping with applicable laws, if human remains are encountered, State Health and Safety Code Section 7050.5 states that no further disturbance shall occur until the County Coroner has made a determination of origin and disposition pursuant to PRC Section 5097.98. The County Coroner must be notified of the find immediately. If the remains are determined to be prehistoric, the Coroner will notify the NAHC, which will determine and notify a MLD (Most Likely Descendent). With the permission of the landowner or his/her authorized representative, the descendent may inspect the site of the discovery. The descendent must complete the inspection within 48 hours of notification by the NAHC. The MLD may recommend scientific removal and nondestructive analysis of human remains and items associated with Native American burials. Therefore, to ensure the preservation of any potential cultural or Paleontological resources, mitigation is warranted to ensure the project will have a less than significant effect on the environment with respect to cultural resources as herein outlined.

Mitigation Measures:

3. *If unanticipated cultural materials are unearthed during construction, work should be halted in the area until a qualified archaeologist can assess the significance of the find. Work may resume immediately a minimum of 50 feet away from the find.*
4. *If human remains are encountered, California Health and Safety Code Section 7050.5 states that no further disturbance shall occur until the Riverside County Coroner has made the necessary findings as to origin. Further, pursuant to California Public Resources Code Section 5097.98(b) remains shall be left in place and free from disturbance until a final decision as to the treatment and disposition has been made. If the Riverside County Coroner determines the remains to be Native American, the Native American Heritage Commission must be contacted within 24 hours. The Native American Heritage Commission must then immediately identify the "most likely descendant(s)" of receiving notification of the discovery. The most likely descendant(s) must then make recommendations within 48 hours and engage in consultations concerning the treatment of the remains as provided in Public Resources Code 5097.98.*
5. *The landowner shall relinquish ownership of all cultural resources, including sacred items, burial goods and all archaeological artifacts that are found on the project area to the appropriate Tribe for proper treatment and disposition which may entail confidential interment at the project site.*
6. *All sacred sites, should they be encountered within the project area, shall be avoided and preserved as the preferred mitigation, if feasible.*
7. *If inadvertent discoveries of subsurface archaeological/cultural resources are discovered during grading, the Developer, a qualified archaeologist, and the Tribe shall assess the significance of such resources and shall meet and confer regarding the mitigation for such resources. Pursuant to Calif. Pub. Res. Code § 21083.2(b) avoidance is the preferred method of preservation for archaeological resources. The project*

archaeologist shall be responsible for determining the significance of the cultural resource and mitigation for such resources. The archeologist shall make the determination based on the provisions of the California Environmental Quality Act with respect to archaeological resources and shall take into account the religious beliefs, customs, and practices of the Tribe(s).

8. *If large fossil specimens are encountered during additional grading, the applicant shall immediately cease operation and retain a qualified and trained paleontologist.*
9. *All fossils collected during the project will be prepared to a reasonable point of identification. Excess sediment or matrix will be removed from the specimens to reduce the bulk and cost of storage. Itemized catalogs of all material collected and identified will be provided to the museum repository along with the specimens.*
10. *A report documenting the results of the monitoring and salvage activities and the significance of the fossils shall be prepared and submitted to the Community Development Department.*

15. AGRICULTURE RESOURCES:

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

a. Williamson Act contract

☐
☐
☐
☒

b. Conversion of farmland to nonagricultural use

☐
☐
☐
☒

Discussion:

The site is not under any agricultural preserve contract pursuant to the Williamson Act as the project site was previously used for mining purposes from as early as 1980 to as late as the 1990's and not for agricultural uses. Therefore, development of the property will not result in impacts to agricultural operations and no mitigation is warranted.

16. GREENHOUSE GAS:

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

a. Generate greenhouse gases

☐☐☒☐

b. Conflict with a plan, policy or regulation

☐☐☐☒**Discussion:**

The City of Corona adopted a Climate Action Plan (CAP) in 2012 which utilizes the *Greenhouse Gas Emissions CEQA Thresholds and Screening Tables* to determine whether or not a project would have a significant impact from greenhouse gas emissions. The screening tables establish options that result in certain levels of greenhouse gas emission reductions attributable to certain design and construction measures incorporated into development projects. Projects that garner at least 100 points will be consistent with the reduction quantities anticipated in the city's CAP and would thus be considered less than significant. Utilizing the screening tables would also contribute to the city's meeting its GHG emissions reductions target or the year 2020.

The residential component on the westerly portion of Planning Area 1 entitled in 2016 under CUP16-002 was evaluated with the city's CAP screening tables proposed by the applicant, and mitigation was applied that required compliance with those point-garnering measures.

The developer has chosen the option to prepare a separate project specific GHG analysis for the commercial component of the project. LDN Consulting, Inc. has prepared an analysis dated August 2, 2018 that calculates GHG emissions related to construction and daily operations utilizing the California Emissions Estimator (CalEEMod) developed for the SCAQMD area and the state's mobile source emission inventory.

Construction activities are not expected to exceed the 3,000-metric ton annual threshold and is considered less than significant (LDN study, Page 3). Operational emissions include energy, mobile, solid waste, water use, and area source emissions which are also estimated using the same CalEEMod calculator. The baseline year is 2008, and the level of emissions for the baseline year in metric tons is 6,240.07. Build-out emissions in 2020 are estimated to be 5,045.80 which is 19.1% under the 2008 baseline year (LDN study, Pages 4-5). This reduction is attributable to increased efficiencies to be implemented through the latest Title 24 Energy standards (2016), water conservation ordinances and standards, construction waste recycling, and other measures that work in concert to reduce overall GHG emissions by the mandated standard of 15% below a Business as Usual benchmark that would exist if all these measures were not implemented. GHG emissions, therefore, are mitigated below a significant level, and no further mitigation is warranted.

17. TRIBAL CULTURAL RESOURCES

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| a. Cause a substantial adverse change in the significance of a tribal cultural resource as defined in Public Resources Code section 21074 that is listed or eligible for listing in the California Register of Historical Resources, or in a local register of historical resources as defined in Public Resources Code section 5020.1(k), or | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| b. A resource determined by the lead agency, in its discretion and supported by substantial evidence, to be significant pursuant to criteria set forth in subdivision (c) of Public Resources Code section 5024.1. | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

Discussion:

See 14 above for a detailed discussion and mitigation measures that apply to Tribal Cultural Resources.

18. MANDATORY FINDING OF SIGNIFICANCE:

Potentially Significant Impact	Potentially Significant Unless Mitigation Incorporated	Less than Significant Impact	No Impact
--------------------------------------	--	------------------------------------	-----------

- | | | | | |
|---|--------------------------|--------------------------|--------------------------|-------------------------------------|
| a. Fish/ wildlife population or habitat or important historical sites | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| b. Cumulatively considerable impacts | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| c. Substantial adverse effects on humans | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| d. Short-term vs. long-term goals | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

Discussion:

The proposed development will not have a significant negative impact on fish or wildlife as the site contains no bodies of water or known wildlife habitat. The site is vacant and previously rough graded with existing commercial development on the adjacent property to the north and major street frontage on three frontages including Interstate 15 along the west site boundary. There is no evidence before the city that the project will have an adverse effect on fish or wildlife resources or cumulatively considerable impacts.

19. PREVIOUS ENVIRONMENTAL ANALYSIS:

Earlier analysis may be used when one or more of the environmental effects have been adequately analyzed in an earlier EIR or Negative Declaration (Section 15063). One or more portions of this Initial Study may have relied upon previous analysis in the Dos Lagos Environmental Impact Report of 2000 (SCH 1999111001), the 2012 IS/MND prepared for the General Plan Amendment (GPA12-003) and Specific Plan Amendment (SPA12-004) adopted December 19, 2012, and the IS/MND prepared for PM 37070 and CUP16-002 adopted July 6, 2016 containing pertinent evaluation related to the subject project site.

DOCUMENTS INCORPORATED BY REFERENCE:

City of Corona, General Plan, March 2004
 Dos Lagos Specific Plan, June 21, 2000
 Annexation 94 and Dos Lagos Specific Plan EIR, David Evans and Associates, June 21, 2000
 IS/MND GPA 12-003, SPA12-004, V12-002, CUP12-005, November 1, 2012
 IS/MND PM 37070 and CUP16-002, July 6, 2016
 Hydrology Study, Land Development Design Company, LLC (LDDC), December 31, 2015.
 Water Quality Management Plan, Land Development Design Company, LLC (LDDC), December 31, 2015.
 Noise Study, LDN Consulting, Inc., January 25, 2016.
 Cultural Resources Technical Report, Cogstone, March 2016.
 Air Quality Screening Letter, LDN Consulting, Inc., January 25, 2016.
 Health Risk Screening Letter, LDN Consulting, Inc., February 16, 2016.
 Greenhouse Gas Emissions Screening Letter, LDN Consulting, Inc., August 2, 2018.
 Traffic Impact Analysis Report, LL&G Engineers, May 21, 2018, Revised July 31, 2018.
 California State Department of Finance, Demographic Research Unit, Table 2: E-5 City/County Pop. and Housing Estimates (related to companion project under CUP16-002).


**MITIGATION MONITORING AND REPORTING PROGRAM
CITY OF CORONA**

No	Mitigation Measures	Implementation Action	Method of Verification	Timing of Verification	Responsible Person	Verification Date
1	<p>Year 2020 With Project Traffic Conditions <i>The results of the Year 2020 With Project intersection capacity analysis presented previously in Table 8-1 indicate that the proposed Project will impact one (1) of the key study intersections. The following improvements listed below have been identified to mitigate the traffic impacts at the intersection impacted by Project traffic:</i></p> <p><u>Temescal Canyon Road at Cajalco Road:</u> Restripe the northbound approach to provide a third exclusive northbound left-turn lane and restripe the shared northbound through/right-turn lane to an exclusive northbound right-turn lane. Install eastbound right-turn overlap traffic signal phasing <u>and restrict</u> northbound U-turn movements.</p>	Conditions of Approval	Plan check and field inspection	Prior to permit issuance and/or C of O	Public Works	
2	<p>Year 2020 With Project Traffic Conditions <i>The developer shall be responsible for a <u>30.36%</u> fair share contribution for the improvements project fair share percentage for the impacted intersection of <u>Temescal Canyon Road at Cajalco Road.</u> As the total cost of the improvements is estimated to be \$20,000, the Project's fair share contribution is approximately \$6,072.00.</i></p>	Conditions of Approval	Plan check and field inspection	Prior to permit issuance and/or C of O	Public Works	
3	<p>If unanticipated cultural materials are unearthed during construction, work should be halted in the</p>	Conditions of	Plan check	During	Field crews,	

	<i>area until a qualified archaeologist can assess the significance of the find. Work may resume immediately a minimum of 50 feet away from the find.</i>	Approval	and inspection	grading operations	inspection and, if warranted, project archaeologist	
4	<i>If human remains are encountered, California Health and Safety Code Section 7050.5 states that no further disturbance shall occur until the Riverside County Coroner has made the necessary findings as to origin. Further, pursuant to California Public Resources Code Section 5097.98(b) remains shall be left in place and free from disturbance until a final decision as to the treatment and disposition has been made. If the Riverside County Coroner determines the remains to be Native American, the Native American Heritage Commission must be contacted within 24 hours. The Native American Heritage Commission must then immediately identify the "most likely descendant(s)" of receiving notification of the discovery. The most likely descendant(s) must then make recommendations within 48 hours and engage in consultations concerning the treatment of the remains as provided in Public Resources Code 5097.98.</i>	Conditions of Approval	Plan check and inspection	During grading operations	Field crews, inspection, and, if warranted, project archaeologist	
5	<i>The landowner shall relinquish ownership of all cultural resources, including sacred items, burial goods and all archaeological artifacts that are found on the project area to the appropriate Tribe for proper treatment and disposition which may entail confidential interment at the project site.</i>	Conditions of Approval	Plan check and inspection	During grading operations	Field crews, inspection and, if warranted, project archaeologist	
6	<i>All sacred sites, should they be encountered within the project area, shall be avoided and preserved as the preferred mitigation, if feasible.</i>	Conditions of Approval	Plan check and inspection	During grading operations	Field crews, inspection and, if warranted, project archaeologist	
7	<i>If inadvertent discoveries of subsurface</i>	Conditions of	Plan check	During	Field crews,	

	<i>archaeological/cultural resources are discovered during grading, the Developer, a qualified archaeologist, and the Tribe shall assess the significance of such resources and shall meet and confer regarding the mitigation for such resources. Pursuant to Calif. Pub. Res. Code § 21083.2(b) avoidance is the preferred method of preservation for archaeological resources. The project archaeologist shall be responsible for determining the significance of the cultural resource and mitigation for such resources. The archeologist shall make the determination based on the provisions of the California Environmental Quality Act with respect to archaeological resources and shall take into account the religious beliefs, customs, and practices of the Tribe(s).</i>	Approval	and inspection	grading operations	inspection and, if warranted, project archaeologist	
8	<i>If large fossil specimens are encountered during additional grading, the applicant shall immediately cease operation and retain a qualified and trained paleontologist.</i>	Conditions of Approval	Plan check and inspection	During grading operations	Field crews, inspection and, if warranted, project archaeologist	
9	<i>All fossils collected during the project will be prepared to a reasonable point of identification. Excess sediment or matrix will be removed from the specimens to reduce the bulk and cost of storage. Itemized catalogs of all material collected and identified will be provided to the museum repository along with the specimens.</i>	Conditions of Approval	Plan check and inspection	During grading operations	Field crews, inspection and, if warranted, project archaeologist	
10	<i>A report documenting the results of the monitoring and salvage activities and the significance of the fossils shall be prepared and submitted to the Community Development Department.</i>	Conditions of Approval	Plan check and inspection	During grading operations	Field crews, inspection and, if warranted, project archaeologist	

AERIAL & ZONING MAP



Date: 08/09/2018

CUP2018-0007



City of Corona

400 S. Vicentia Ave.
Corona, CA 92882



Minutes - Draft

Monday, August 20, 2018

6:00 PM

Council Chambers

Planning and Housing Commission

Mitchell Norton, Chair
Timothy Jones, Vice Chair
Yolanda Carrillo, Commissioner
Tony Dunn, Commissioner
Jeff Ruscigno, Commissioner

EXHIBIT 4

Rollcall

Present 4 - Yolanda Carrillo, Tim Jones, Mitchell Norton, and Jeff Ruscigno

Absent 1 - Tony Dunn

1. CALL TO ORDER

Chair Norton called the meeting to order.

2. PLEDGE OF ALLEGIANCE

Vice Chair Jones led the Pledge of Allegiance.

3. ORAL COMMUNICATIONS FROM THE PUBLIC

None.

4. MEETING MINUTES

18-1974 Approval of minutes for the Planning and Housing Commission meeting of July 9, 2018.

Attachments: 20180709-P&H Minutes - DRAFT

A motion was made by Commissioner Ruscigno, seconded by Vice Chair Jones, that the Planning and Housing Commission approve the meeting minutes of July 9, 2018. The motion carried by the following vote:

Aye: 4 - Carrillo, Jones, Norton, and Ruscigno

Absent: 1 - Dunn

18-2044 Approval of minutes for the Planning and Housing Commission meeting of July 23, 2018.

Attachments: 20180723-P&H Minutes - DRAFT

A motion was made by Commissioner Ruscigno, seconded by Vice Chair Jones, that the Planning and Housing Commission approve the meeting minutes of July 23, 2018. The motion carried by the following vote:

Aye: 4 - Carrillo, Jones, Norton, and Ruscigno

5. CONSENT ITEMS

None.

6. PUBLIC HEARINGS

18-2034 CZ2018-0001: Application to change the zone on approximately 0.2 acres from MP (Mobile Home Park) to C-3 (General Commercial) located

approximately 350 feet west of Lincoln Avenue, north of Sixth Street, and that the Planning and Housing Commission recommend adoption of the Negative Declaration and APPROVAL of CZ2018-0001 to the City Council based on the findings contained in the staff report. (Applicant: Fitschen Family Trust, 1203 W. Sixth Street Corona CA 92882).

Attachments: Locational and Zoning Map

Exhibit A - Existing and Proposed zoning map amendment

Exhibit B - Applicant's letter dated March 29, 2018

Exhibit C - Legal Description and plat of the change of zone project site

Exhibit D - Environmental Documentation

CZ2018-0001 PM2018-0001 Presentation

Chair Norton opened the Public Hearing.

Chair Norton closed the Public Hearing.

Commissioner Ruscigno stated it is a good idea.

Commissioner Ruscigno asked if this used to be a lounge for a long time.

Commissioner Carrillo stated yes.

A motion was made by Carrillo, seconded by Jones, that the Planning and Housing Commission recommend adoption of the Negative Declaration and APPROVAL of CZ2018-0001 to the City Council based on the findings contained in the staff report. The motion carried by the following vote:

Aye: 4 - Carrillo, Jones, Norton, and Ruscigno

18-2022

PM37452 (PM2018-0001): Parcel map application to subdivide 8.81 acres into two parcels located approximately 350 feet west of Lincoln Avenue, north of Sixth Street in the MP (Mobile Home Park) Zone and proposed C-3 (General Commercial) Zone on 0.20 acres and that the Planning and Housing Commission recommend adoption of the Negative Declaration and APPROVAL of PM37452 to the City Council, based on the findings contained in the staff report and subject to the conditions of approval. (Applicant: Fitschen Family Trust, 1203 W. Sixth Street Corona CA 92882).

Attachments: Locational and Zoning Map

Exhibit A - Parcel Map 37452

Exhibit B - Conditions of Approval

Exhibit C - Applicant's letter dated March 27, 2018

Exhibit D - Environmental Documentation

Exhibit E - GIS Aerial Map

A motion was made by Ruscigno, seconded by Jones, that the Planning and Housing Commission recommend adoption of the Negative Declaration and APPROVAL of PM37452 to the City Council, based on the findings contained in the staff report and subject to the conditions of approval. The motion carried by the following vote:

Aye: 4 - Carrillo, Jones, Norton, and Ruscigno

18-2032 PP2018-0003: Application for a Precise Plan review of a proposed 90,865 square foot commercial development including a four-story hotel, 11,000 square feet of restaurant space including a drive-through, 15,800 square feet of retail floor area including a convenience store with a 10-pump fuel station and 2,000 square foot ancillary drive-through car wash on 7.3 acres in the Commercial designation (Planning Area 1) of the Dos Lagos Specific Plan (SP-99-03) and that the Planning and Housing Commission adopt the Mitigated Negative Declaration and Mitigation Monitoring Plan and adopt Resolution No. 2514 GRANTING PP2018-0003 based on the findings contained in the staff report and conditions of approval. (Applicant: Terrano Plaza, Inc., Rexco).

Attachments: Resolution No. 2514

Locational and Zoning Map

Exhibit A-1 and A-2 - Site Plan

Exhibit B - Conditions of Approval

Exhibit C-1 - C-5 - (North) Hotel Elevations, Floor Plans and Material Palette

Exhibit D-1 - D-2 - (North) Buildings B and C Elevations and shell Floor Plans

Exhibit E-1 - E-3 - (South) Buildings A and Drive-through Elevations and shell Floor Plans

Exhibit F-1 - F-6 - Convenience store and Fuel Station Rendering, Elevations and Material Palette, and Floor Plan

Exhibit G - Conceptual Landscape Plan

Exhibit H-1 - H-6 - Conceptual Sign Program

Exhibit I - Applicant's letter dated May 1, 2018

Exhibit J - Letter dated August 8, 2018 from Temescal Canyon, LLC, in support of the project

Exhibit K - Environmental Documentation with aerial exhibit

PP2018-0003 and CUP2018-0007

Commissioner Ruscigno asked about the open tunnel of the car wash and landscape screening for the visual and sound aspects of it.

TERRI MANUEL, PLANNING MANAGER, stated that the operation would be from 6 a.m. to 10 p.m., although the convenience store will operate 24 hours. The applicant has stated that the hours will be limited from 6 a.m. to 10 p.m. Staff can ensure that additional landscaping is placed at key locations to visually buffer it from the right-of-way.

Commissioner Ruscigno asked about the landscaping and trellises above the gas pumps and how they would be maintained if it is completely covered.

Ms. Manuel stated that she imagines it will be a drip design and it would be something their landscape architect would have to address in terms of getting enough sunlight.

Commissioner Ruscigno stated that he is trying to get the concept that is presented as it appears different compared to mediterranean design.

Vice Chair Jones asked if the hours of operation are indicated in the conditions of approval.

Ms. Manuel stated that she does not believe they were added as a condition of approval as staff relies on that from the applicant's representation.

Vice Chair Jones stated, on the concern of the potential noise late at night, that there is no guarantee those hours would stand. He said he would also like to see more landscaping for the sound attenuation around the car wash.

Ms. Manuel stated that staff can add those as two additional separate conditions of approval.

Chair Norton asked if the precise identity of the tenants for the restaurants are yet to be determined.

Ms. Manuel stated that is staff's understanding.

Commissioner Ruscigno asked if they would eventually subdivide the property now or later

Ms. Manuel stated that the applicant intends to do a lot line adjustment subject to Board of Zoning Adjustment approval. If they are increasing the number of lots, they would bring it back as a Parcel Map.

Commissioner Ruscigno asked if there is only one parcel.

CHRIS HORN, SENIOR ENGINEER, stated there are currently three parcels, and there will be a lot line adjustment on the south part of the property between car wash and the retail spaces. The developer has discussed how they would handle the subdivision of the north side of the

site, and the would potentially have an option to do a Parcel Map waiver.

Chair Norton opened the Public Hearing.

Chair Norton closed the Public Hearing.

A motion was made by Carrillo, seconded by Ruscigno, that the Planning and Housing Commission adopt the Mitigated Negative Declaration and Mitigation Monitoring Plan and adopt Resolution No. 2514 GRANTING PP2018-0003 based on the findings contained in the staff report and conditions of approval. The motion carried by the following vote:

Aye: 4 - Carrillo, Jones, Norton, and Ruscigno

Absent: 1 - Dunn

18-2033

CUP2018-0007: Conditional Use Permit for a 2,000 square foot drive-through car wash to be located on the south side of a convenience store as part of a commercial development proposed at the northwest corner of Dos Lagos Drive and Temescal Canyon Road in the Commercial designation of the Dos Lagos Specific Plan (SP-99-03), and that the Planning and Housing Commission recommend adoption of the Mitigated Negative Declaration and Mitigation Monitoring Plan and Resolution No. 2515 GRANTING CUP2018-0007, based on the findings contained in the staff report and conditions of approval. (Applicant: Terrano Plaza, LLC - Rexco).

Attachments: Resolution 2515

Locational and zoning map

Exhibit A - Site Plan

Exhibit B - Conditions of Approval

Exhibit C-1 - C-2 - Elevations

Exhibit D - Floor Plan

Exhibit E - Applicant's letter dated May 8, 2018

Exhibit F - Environmental Documentation with aerial exhibit

A motion was made by Ruscigno, seconded by Jones, that the Planning and Housing Commission recommend adoption of the Mitigated Negative Declaration and Mitigation Monitoring Plan and Resolution No. 2515 GRANTING CUP2018-0007, based on the findings contained in the staff report and conditions of approval.. The motion carried by the following vote:

Aye: 4 - Carrillo, Jones, Norton, and Ruscigno

7. WRITTEN COMMUNICATIONS

None.

8. ADMINISTRATIVE REPORTS

None.

9. PLANNING AND HOUSING COMMISSIONERS' REPORTS AND COMMENTS

None.

10. ADJOURNMENT

Chair Norton adjourned the meeting at 6:37 p.m. to the Planning and Housing Commission meeting of Monday, September 10, 2018, commencing at 6:00 p.m. in the City Hall Council Chambers.